EXHIBIT A

PROPONENT'S ENVIRONMENTAL ASSESSMENT

Lakeville–Sonoma 115 kV Transmission Line Project

Pacific Gas and Electric Company
245 Market Street, N10A
San Francisco, CA 94105

Contacts:
Jo Lynn Lambert (415) 973-5248
David Kraska (415) 973-7503

Prepared by:
EDAW, Inc.
150 Chestnut Street
San Francisco, CA 94111

NOVEMBER 2004

LAKEVILLE-SONOMA 115 kV TRANSMISSION LINE PROJECT

PROPONENT'S ENVIRONMENTAL ASSESSMENT

TABLE OF CONTENTS

1.0 EXECUTIVE SUMMARY 1-1

2.0 PROJECT DESCRIPTION 2-1

2.1 Project Overview 2-1

2.1.1 Existing Regional Electric System 2-3

2.1.1.1 - Existing Substations 2-4

2.1.1.2 - Existing 115 kV Transmission Facilities 2-7

2.1.1.3 - Existing Generation Facilities 2-7

2.2 Project Purpose and Need 2-7

2.3 Description of the Project 2-12

2.3.1 Project Components 2-12

2.3.1.1 - 115 kV Transmission Line 2-12

2.3.1.2 - Substations 2-20

2.4 Construction 2-23

2.4.1 Transmission Line Construction 2-23

2.4.1.1 - Line Staging Areas 2-23

2.4.1.2 - Pull and Tension Sites 2-24

2.4.1.3 - Access Roads 2-25

2.4.1.4 - Helicopter Access 2-26

2.4.1.5 - Traffic Control 2-26

2.4.1.6 - Right-of-Way (ROW) Requirements and Preparation 2-27

2.4.1.7 - Vegetation Clearance 2-27

2.4.1.8 - Pole Removal, Top Removal, and Installation 2-28

2.4.1.9 - Helicopter Pole Installation 2-31

2.4.1.10 - Conductor Installation 2-31

2.4.1.11 - Cleanup and Post-Construction Restoration 2-32

2.4.2 Substation Modifications and Construction 2-34

2.4.3 Construction Workforce and Equipment 2-34

2.5 Operation and Maintenance Procedures 2-36

2.5.1 General System Monitoring and Control 2-36
2.5.2 Facility Inspection 2-36
2.5.3 Maintenance Procedures 2-36
2.6 Permit Requirements 2-37
2.7 Schedule 2-39
2.8 References 2-39
3.0 ALTERNATIVES TO THE PROPOSED PROJECT 3-1
3.1 Introduction 3-1
3.2 Description Alternatives 3-3
3.2.1 Alternative 1 3-3
3.2.2 Alternative 2 3-3
3.2.3 Alternative 3 3-3
3.2.4 Alternative 4 3-4
3.2.5 No Project Alternative 3-4
3.2.6 CEQA Analysis of Alternatives 3-4
3.3 Development of Alternatives and Selection of the Proposed Project 3-9
3.4 Comparison of Alternatives 3-9
3.4.1 Proposed Project – Summary of Environmental Impacts 3-9
3.4.2 Alternative 1 – Summary of Environmental Impacts 3-11
3.4.3 Alternative 2 – Summary of Environmental Impacts 3-12
3.4.4 Alternative 3 – Summary of Environmental Impacts 3-14
3.4.5 Alternative 4 – Summary of Environmental Impacts 3-15
3.4.6 No Project Alternative – Summary of Environmental Impacts 3-16
3.5 Analysis of Alternate Transmission Line Routes 3-16
3.5.1 Alternative 1 – Segments 1, 3, 12, 11, 9, 8, 7, 5, 6 3-16
3.5.1.1 - Air Quality 3-16
3.5.1.2 - Biological Resources 3-17
3.5.1.3 – Cultural Resources 3-17
3.5.1.4 - Energy and Utilities 3-19
3.5.1.5 – Geology 3-19
3.5.1.6 - Hydrology and Water Quality 3-19
3.5.1.7 - Land Use and Agriculture 3-20
3.5.1.8 – Noise 3-20
3.5.1.9 - Public Health and Safety 3-20
3.5.1.10 - Transportation and Traffic 3-20

3.5.1.11 - Visual Resources 3-27
3.5.1.12 - Corona and Induced Current Effects 3-31
3.5.1.13 - Growth Inducing Impacts 3-31
3.5.1.14 - Cumulative Impacts 3-31
3.5.2 Alternative 2 – Segments 1, 2, 13, 12, 4, 5, 6 3-31
3.5.2.1 – Air Quality 3-31
3.5.2.2 - Biological Resources 3-31
3.5.2.3 – Cultural Resources 3-32
3.5.2.4 - Energy and Utilities 3-32
3.5.2.5 – Geology 3-32
3.5.2.6 - Hydrology and Water Quality 3-32
3.5.2.7 - Land Use and Agriculture 3-32
3.5.2.8 – Noise 3-33
3.5.2.9 - Public Health and Safety 3-33
3.5.2.10 - Transportation and Traffic 3-33
3.5.2.11 - Visual Resources 3-33
3.5.2.12 - Corona and Induced Current Effects 3-35
3.5.2.13 - Growth Inducing Impacts 3-35
3.5.2.14 - Cumulative Impacts 3-35
3.5.3 Alternative 3 – Segments 14, 10, 11, 4, 5, 6 3-35
3.5.3.1 – Air Quality 3-35
3.5.3.2 - Biological Resources 3-35
3.5.3.3 – Cultural Resources 3-36
3.5.3.4 - Energy and Utilities 3-36
3.5.3.5 – Geology 3-36
3.5.3.6 - Hydrology and Water Quality 3-36
3.5.3.7 - Land Use and Agriculture 3-37
3.5.3.8 – Noise 3-37
3.5.3.9 - Public Health and Safety 3-37
3.5.3.10 - Transportation and Traffic 3-37
3.5.3.11 - Visual Resources 3-37
3.5.3.12 - Corona and Induced Current Effects 3-38
3.5.3.13 - Growth Inducing Impacts 3-38
3.5.3.14 - Cumulative Impacts 3-38
3.5.4 Alternative 4 – Segments 14, 15, 16, 8, 7, 5, 6 3-38
3.5.4.1 – Air Quality 3-38
3.5.4.2 - Biological Resources 3-39
3.5.4.3 – Cultural Resources 3-39
3.5.4.4 - Energy and Utilities 3-40
3.5.4.5 – Geology 3-40
3.5.4.6 - Hydrology and Water Quality 3-40

3.5.4.7 - Land Use and Agriculture 3-40
3.5.4.8 – Noise 3-40
3.5.4.9 - Public Health and Safety 3-41
3.5.4.10 - Transportation and Traffic 3-41
3.5.4.11 - Visual Resources 3-41
3.5.4.12 - Corona and Induced Current Effects 3-43
3.5.4.13 - Growth Inducing Impacts 3-43
3.5.4.14 - Cumulative Impacts 3-43
3.6 No Project Alternative 3-43
3.7 References 3-44
4.0 IMPACT ASSESSMENT SUMMARY 4-1
4.1 CEQA Appendix G: Environmental Checklist Form 4-1
4.2 Environmental Issues 4-3
4.2.1 Aesthetics 4-3
4.2.2 Agricultural Resources 4-4
4.2.3 Air Quality 4-5
4.2.4 Biological Resources 4-6
4.2.5 Cultural Resources 4-8
4.2.6 Geology and Soils 4-9
4.2.7 Hazards and Hazardous Materials 4-11
4.2.8 Hydrology and Water Quality 4-13
4.2.9 Land Use and Planning 4-16
4.2.10 Mineral Resources 4-17
4.2.11 Noise 4-18
4.2.12 Population and Housing 4-19
4.2.13 Public Services 4-20
4.2.14 Recreation 4-20
4.2.15 Transportation and Traffic 4-21
4.2.16 Utilities and Service Systems 4-22
4.2.17 Mandatory Findings of Significance 4-24
5.0 AIR QUALITY 5-1
5.1 Introduction 5-1
5.1.1 Methodology 5-1
5.1.2 Applicable Laws and Regulations 5-2
5.1.2.1 - Federal Air Quality Regulations 5-2

5.1.2.2 - State Air Quality Regulations 5-4
5.1.2.3 - Regional and Local Air Quality Regulations 5-4
5.2 Existing Conditions 5-5
5.2.1 Regional Topography, Meteorology, and Climate 5-5
5.2.2 Regional Air Quality 5-6
5.2.2.1 - Ozone 5-6
5.2.2.2 - Particulate Matter PM 5-7
5.3 Potential Impacts 5-8
5.3.1 Significance Criteria 5-8
5.3.2 Construction Impacts 5-9
5.3.3 Operational Impacts 5-12
5.4 Mitigation Measures 5-13
5.5 References 5-13
6.0 BIOLOGICAL RESOURCES 6-1
6.1 Introduction and Methods 6-1
6.1.1 Overview of Survey Methods 6-1
6.1.2 Vegetation and Wetlands Methods 6-1
6.1.3 Wildlife Habitat Assessment Methods 6-2
6.1.4 Special-status Species Survey Methods 6-3
6.1.4.1 - Special-status Plant Surveys 6-3
6.1.4.2 - Special-status Wildlife Surveys 6-4
6.2 Regulatory Framework 6-7
6.2.1 Federal Regulations 6-7
6.2.1.1 - Federal Regulation of Waters of the United States, Including Wetlands (Clean Water Act Sections 404 and 401) 6-7
6.2.1.2 - Federal Policies on Riparian Communities in California 6-8
6.2.1.3 - Federal Endangered Species Act 6-8
6.2.1.4 - Federal Migratory Bird Treaty Act 6-9
6.2.1.5 - Bald and Golden Eagle Protection Act 6-9
6.2.1.6 - Federal Regulations on Interstate Transport of the Sudden Oak Death Pathogen 6-9
6.2.2 State and Local Regulations 6-9
6.2.2.1 - State Regulation of Waters 6-9
6.2.2.2 - Storm Water Pollution Prevention Plan 6-10
6.2.2.3 - California Endangered Species Act 6-10
6.2.2.4 - California Fish and Game Code Bird Protections 6-11
6.2.2.5 - Native and Heritage Tree Ordinances 6-11

6.2.2.6 - State and Local Regulations on the Transport of the SOD Pathogen 6-12
6.2.2.7 - Sonoma County General Plan Policy for Riparian Corridors 6-12
6.3 Existing Conditions.....6-12
6.3.1 Vegetation and Habitat Types.....6-13
6.3.1.1 – Substations 6-13
6.3.1.2 - Transmission Line 6-13
6.3.1.3 - Upland Vegetation Types 6-14
6.3.1.4 - Wetland and Riparian Vegetation Types.....6-20
6.3.2 Wetland and Aquatic Resources 6-24
6.3.3 Wildlife Habitats.....6-25
6.3.4 Special-status Species.....6-28
6.3.4.1- Plants 6-28
6.3.4.2 – Wildlife 6-36
6.4 Potential Impacts and Mitigation Measures.....6-54
6.4.1 Significance Criteria.....6-55
6.4.2 Construction Impacts and Mitigation Measures.....6-56
6.4.2.1 - Substation Impacts.....6-57
6.4.2.2 - Transmission Line Impacts 6-58
6.4.3 Operation and Maintenance Impacts and Mitigation Measures.....6-70
6.4.3.1 - Substation Impacts.....6-70
6.4.3.2 - Transmission Line Impacts 6-70
6.5 References.....6-72
6.5.1 Literature Cited 6-72
6.5.2 Personal Communications 6-76
7.0 CULTURAL RESOURCES 7-1
7.1 Introduction and Methodology 7-1
7.1.1 Prehistoric Background.....7-1
7.1.1.1 - Paleo-Indian Period (10000 B.C. to 6000 B.C.) 7-1
7.1.1.2 - Lower Archaic Period (6000 B.C. to 3000 B.C.) 7-1
7.1.1.3 - Middle Archaic Period (3000 B.C. to 1000 B.C.) 7-2
7.1.1.4 - Upper Archaic Period (1000 B.C. to A.D. 500) 7-2
7.1.1.5 - Emergent Period (A.D. 500 to A.D. 1800).....7-2
7.1.2 Ethnographic Background.....7-3
7.1.2.1 – Wappo.....7-3
7.1.2.2 - Coast Miwok 7-3
7.1.2.3 – Patwin 7-4
7.1.3 Historic Background 7-5

7.1.3.1 - Napa Valley History 7-5
7.1.3.2 - Sonoma History 7-6
7.2 Regulatory Framework 7-7
7.2.1 CEQA Guidelines 7-7
7.3 Existing Conditions 7-8
7.3.1 Affected Environment 7-8
7.4 Potential Impacts and Mitigation Measures 7-10
7.4.1 Known Cultural Resources 7-10
7.4.2 Unknown Cultural Resources 7-11
7.5 References 7-12
7.5.1 Literature Cited 7-12
7.5.2 Websites Accessed 7-14
8.0 ENERGY AND UTILITIES 8-1
8.1 Introduction and Methodology 8-1
8.2 Existing Conditions 8-1
8.3 Potential Impacts and Mitigation Measures 8-1
8.3.1 Significance Criteria 8-1
8.3.2 Construction Impacts 8-2
8.3.3 Operation Impacts 8-2
8.4 References 8-3
9.0 GEOLOGY 9-1
9.1 Introduction and Methodology 9-1
9.1.1 Methodology 9-1
9.2 Regulatory Framework 9-2
9.3 Existing Conditions 9-2
9.3.1 Topography 9-2
9.3.2 Geology 9-2
9.3.2.1 - Geologic Structure 9-3
9.3.2.2 - Surficial Deposits 9-3
9.3.2.3 – Bedrock 9-4
9.3.2.4 - Subsurface Exploration 9-4
9.3.3 Soils 9-4
9.3.3.1 - Soil Associations 9-7
9.3.4 Mineral Resources 9-7
9.3.4.1 - Sand and Gravel Quarries 9-8

9.3.4.2 - Oil and Minerals....9-8
9.3.4.3 - Hydrothermal Resources....9-8
9.3.5 Paleontology....9-9
9.3.6 Seismicity....9-9
9.3.6.1 - Seismic Parameters....9-10
9.3.6.2 - Fault Classification and Zoning....9-13
9.3.6.3 - Alquist-Priolo Earthquake Fault Zones....9-14
9.3.6.4 - Faults in the Project Area....9-17
9.4 Potential Impacts and Mitigation Measures....9-18
9.4.1 Significance Criteria....9-18
9.4.2 Summary of Potential Geologic, Seismic, and Geotechnical Hazards....9-19
9.4.3 Construction Related Impacts....9-20
9.4.4 Operation Impacts....9-22
9.5 References....9-27
10.0 HYDROLOGY AND WATER QUALITY....10-1
10.1 Introduction and Methodology....10-1
10.2 Regulatory Framework....10-1
10.2.1 Federal and State Permit Requirements....10-2
10.2.2 Local Permit Requirements....10-2
10.3 Existing Conditions....10-2
10.3.1 Surface Water Hydrology....10-2
10.3.1.1 – Sonoma Creek Watershed....10-2
10.3.1.2 – Petaluma River Watershed....10-5
10.3.1.3 – Ponds, Reservoirs, and Wetlands....10-5
10.3.2 Precipitation and Infiltration....10-6
10.3.3 Storm Water Management System and Flooding Potential....10-6
10.3.4 Surface Water Quality....10-7
10.3.5 Groundwater Quality and Use....10-8
10.3.5.1 – Petaluma Valley Groundwater Basin....10-8
10.3.5.2 – Sonoma Valley Groundwater Basin....10-9
10.4 Potential Impacts and Mitigation Measures....10-9
10.4.1 Significance Criteria....10-9
10.4.2 Construction Impacts....10-10
10.4.3 Operation Impacts....10-11
10.5 References....10-12

11.0 LAND USE AND AGRICULTURE 11-1
11.1 Introduction and Methodology 11-1
11.2 Regulatory Framework 11-1
11.2.1 Jurisdictions 11-1
11.2.1.1 - California Public Utilities Commission 11-1
11.2.1.2 - Sonoma County 11-1
11.2.1.3 - City of Sonoma 11-2
11.2.1.4 - City of Petaluma 11-2
11.2.1.5 - California Department of Transportation 11-2
11.2.2 Plans and Policies 11-2
11.2.2.1 - Segments 1, 2, and most of 17 11-2
11.2.2.2 - Segment 17 – Sonoma Substation 11-10
11.3 Existing Conditions 11-12
11.3.1 General Plan Land Use Designations and Existing Land Uses 11-13
11.3.1.1 - Lakeville Substation 11-13
11.3.1.2 - Segment 1 11-13
11.3.1.3 - Segment 2 11-14
11.3.1.4 - Segment 17 11-14
11.3.1.5 - Sonoma Substation 11-17
11.3.2 Planned and Proposed Development 11-17
11.3.2.1 - Segment 1 11-17
11.3.2.2 - Segment 2 11-17
11.3.2.3 - Segment 17 11-18
11.4 Potential Impacts and Mitigation Measures 11-18
11.4.1 Significance Criteria 11-18
11.4.1.1 - Overview of Impact Analysis 11-18
11.4.2 Construction Impacts 11-24
11.4.2.1 – Substations 11-24
11.4.2.2 - Transmission Line 11-24
11.4.2.3 - Staging Areas 11-24
11.4.3 Operation Impacts 11-24
11.4.3.1 – Substation 11-24
11.4.3.2 - Transmission Line 11-25
11.4.3.3 - Consistency with Local General Plans and Policies 11-27
11.5 References 11-29
12.0 NOISE 12-1
12.1 Introduction 12-1
12.1.1 Methodology 12-2

12.1.2 Applicable Laws and Regulations 12-2
12.1.2.1 - Sonoma County 12-4
12.1.2.2 - City of Sonoma 12-4
12.2 Existing Conditions 12-5
12.2.1 Sensitive Receptors 12-6
12.2.2 Transmission Line Route 12-7
12.2.3 Substation Sites 12-7
12.3 Potential Impacts 12-8
12.3.1 Significance Criteria 12-8
12.3.2 Construction Impacts 12-9
12.3.2.1 - Transmission Line Construction 12-9
12.3.3 Operational Impacts 12-11
12.3.3.1 - Transmission Line Operation 12-11
12.3.3.2 - Substation Operation 12-11
12.4 References 12-12
12.5 Glossary 12-13
13.0 PUBLIC HEALTH AND SAFETY, AND HAZARDOUS MATERIALS 13-1
13.1 Introduction and Methodology 13-1
13.2 Regulatory Framework 13-2
13.3 Existing Conditions 13-4
13.4 Potential Impacts and Mitigation Measures 13-7
13.4.1 Significance Criteria 13-7
13.4.2 Construction Impacts 13-7
13.4.3 Operation Impacts 13-9
13.5 References 13-10
14.0 TRANSPORTATION AND TRAFFIC 14-1
14.1 Introduction and Methodology 14-1
14.2 Regulatory Framework 14-1
14.2.1 State Regulations 14-1
14.2.1.1 - Sonoma County 14-2
14.2.1.2 - City of Sonoma 14-3
14.3 Existing Conditions 14-3
14.3.1 Interstate and State Highways 14-3
14.3.1.1 - State Route 12 14-4
14.3.1.2 - State Route 116 14-4

14.3.2 Other Roadways 14-4
14.3.3 Public Transit 14-4
14.3.4 Rail Service 14-5
14.3.5 Bicycle and Pedestrian Transportation 14-5
14.4 Potential Impacts and Mitigation Measures 14-5
14.4.1 Significance Criteria 14-6
14.4.2 Construction Impacts 14-6
14.4.3 Operation Impacts 14-8
14.5 References 14-8
15.0 VISUAL RESOURCES 15-1
15.1 Introduction and Methodology 15-1
15.1.1 Visual Simulation Methodology 15-2
15.1.1.1 - Site Reconnaissance/Photography 15-3
15.1.1.2 - Computer Modeling 15-3
15.1.1.3 - Photo-Editing 15-5
15.2 Regulatory Framework 15-5
15.2.1 Summary of Adopted Plans and Policies 15-5
15.2.1.1 - CPUC Policies 15-6
15.2.1.2 - Sonoma County General Plan 15-6
15.2.1.3 - City of Sonoma General Plan 15-8
15.2.1.4 - California State Scenic Highways Program 15-12
15.3 Existing Conditions 15-13
15.3.1 Regional and Local Setting 15-13
15.3.2 Landscape Units 15-13
15.4 Potential Impacts and Mitigation Measures 15-26
15.4.1 Significance Criteria 15-26
15.4.2 Construction Impacts 15-27
15.4.3 Operation Impacts 15-28
15.5 References 15-35
15.5.1 Personal Communications 15-36
16.0 CORONA AND INDUCED CURRENT EFFECTS 16-1
16.1 Introduction and Methodology 16-1
16.2 Regulatory Framework 16-1
16.3 Existing Conditions 16-1
16.3.1 Induced Currents, Shock, Fuel Ignition, Fires, Lightning, and

Cardiac Pacemakers 16-1
16.3.1.1 – Lightning 16-3
16.3.1.2 - Corona, Radio and Television Interference, and Computer Monitor Interference 16-3
16.4 Potential Impacts and Mitigation Measures 16-4
16.4.1 Significance Criteria 16-4
16.4.2 Construction Impacts 16-4
16.4.3 Operation Impacts 16-5
16.4.3.1 - Induced Currents, Shock, Fuel Ignition, Fires, Lightning, and Cardiac Pacemakers 16-5
16.4.3.2 - Corona, Radio and Television Interference, and Computer Monitor Interference 16-8
16.5 References 16-11
17.0 GROWTH INDUCING IMPACTS 17-1
17.1.1 - Economic or Population Growth 17-1
17.1.2 - Extended Access or Public Services 17-3
17.2 References 17-4
18.0 CUMULATIVE IMPACTS 18-1
18.1 Introduction 18-1
18.2 Methodology 18-1
18.3 Analysis of Cumulative Impacts 18-2
18.3.1 - Air Quality 18-2
18.3.2 - Biological Resources 18-2
18.3.3 - Cultural Resources 18-9
18.3.4 - Energy and Utilities 18-9
18.3.5 – Geology 18-9
18.3.6 - Hydrology and Water Quality 18-9
18.3.7 - Land Use and Agriculture 18-9
18.3.8 – Noise 18-9
18.3.9 - Public Health and Safety 18-10
18.3.10 - Transportation and Traffic 18-10
18.3.11 - Visual Resources 18-10
18.3.12 - Corona and Induced Current Effects 18-11
18.3.13 - Growth Inducing Impacts 18-11
18.4 Conclusion 18-12
18.5 References 18-12

19.0 MITIGATION MONITORING PLAN 19-1
19.1 Mitigation Monitoring 19-1
19.2 Mitigation Enforcement 19-1

APPENDICES:

A – Erosion Control and Restoration Plan
B – Sonoma County Native and Heritage Tree Ordinances
C – Visual Simulations
D – Affected Property Owners
E – List of Preparers
F – Glossary
G – Native American Contacts
H – Electric and Magnetic Fields
I – Construction Plan
J – Sudden Oak Death Guidelines

LIST OF TABLES

Table 2-1 Summary of Project Components 2-1
Table 2-2 115 kV Transmission Line Construction 2-14
Table 2-3 Summary of Pole Installation Metrics 2-31
Table 2-4 Crews Expected to be Used During Project Construction 2-34
Table 2-5 Equipment Expected to be Used During Project Construction 2-35
Table 2-6 Summary of Permit Requirements 2-37
Table 2-7 Construction Schedule 2-39
Table 3-1 Alternatives by Segment 3-1
Table 3-2 15 kV Transmission Line Construction (for all segments and alternatives) 3-2
Table 3-4 Special-Status Species Observed or Documented Along Alternative Route Segments 3-18
Table 3-6 Mapped Soil Associations in Project Area 3-23
Table 3-7 Known Active and Potentially Active Faults – Lakeville Substation 3-25
Table 3-8 Known Active and Potentially Active Faults – Sonoma Substation 3-26
Table 5-1 Federal and State Air Quality Standards and Bay Area Attainment Status 5-3
Table 5-2 Ozone and Particulate Matter Monitoring Data 5-8
Table 5-3 Construction Emissions Estimates 5-10
Table 5-4 2001 Bay Area Annual Average Emissions by Source Category 5-11
Table 5-5 Operational Emissions Estimates 5-13
Table 6-1 Wildlife Habitats and Corresponding Vegetation Types. 6-25
Table 6-2 Special-Status Plant Species with Potential to Occur in the Project Area 6-29
Table 6-3 Special-Status Wildlife Species with Potential to Occur in the Project Area 6-39
Table 6-4 Special-Status Species Observed or Documented within the Project Area. 6-54
Table 9-1 Mapped Soil Associations in Project Area 9-5
Table 9-2 Known Active and Potentially Active Faults – Lakeville Substation 9-15
Table 9-3 Known Active and Potentially Active Faults – Sonoma Substation 9-16
Table 11-1 Properties Crossed by Transmission Line Project 11-5
Table 11-2 Land Use Designations 11-8
Table 11-3 Land Use 11-12
Table 11-4 Proposed City of Sonoma Development 11-19
Table 11-5 Proposed Sonoma County Developments (large scale developments only) 11-21

Table 11-6 Other Planned Infrastructure Projects 11-22
Table 12-1 Noise Measurement Results (A-Weighted Decibels [dBA]) 12-7
Table 12-2 Typical Noise Levels Generated by Construction Equipment 12-9
Table 13-1 Vicinity Sites With Known Hazardous Material Releases 13-4
Table 14-1 Local and County Roads 14-2
Table 15-2 Summary of Effects Shown in Visual Simulations 15-37
Table 18-1 List of Reasonably Foreseeable Future Projects 18-3
Table 19-1 Mitigation Monitoring Plan 19-2

LIST OF FIGURES

Figure 2-1: Proposed Project 2-3
Figure 2-2: Existing Regional Electric System 2-5
Figure 2-3: Typical Electric Transmission System 2-4
Figure 2-4a: Proposed Transmission Line Route West 2-15
Figure 2-4b: Proposed Transmission Line Route Mid-West 2-16
Figure 2-4c: Proposed Transmission Line Route Mid-East 2-17
Figure 2-4d: Proposed Transmission Line Route East 2-18
Figure 2-5: Typical Pole Designs 2-19
Figure 2-6: Lakeville Substation Modifications 2-21
Figure 2-7: Sonoma Substation Modifications 2-22
Figure 2-8: Conductor Reels and Tensioning Device at Pull Site 2-24
Figure 2-9: Tree Trimming Diagram 2-27
Figure 2-10: Track Auger 2-30
Figure 2-11: Y-Frame Structure 2-33
Figure 3-1: Proposed Project and Alternatives 3-5
Figure 3-2: Study Area and Route Segment Alternatives 3-6
Figure 3-3a: Alternative Route Segments on Aerial Photos (West) 3-7
Figure 3-3b: Alternative Route Segments on Aerial Photos (East) 3-8
Figure 3-4: Generalized Geologic Map 3-21
Figure 3-5: Generalized Soil Association Map 3-22

Figure 3-6: Scenic Road Corridors 3-29
Figure 6-1a: Wetlands and Aquatic Resources (West) 6-15
Figure 6-1b: Wetlands and Aquatic Resources (East) 6-16
Figure 6-2: Results of Special Plant Surveys 6-33
Figure 6-3: Special Status Wildlife CNDDB Records and Field Observations 6-37
Figure 9-1: Fault Map 9-11
Figure 10-1: Watersheds 10-3
Figure 10-2: FEMA Flood Zones 10-4
Figure 11-1: Jurisdictions and Public Land Uses 11-3
Figure 11-2: Sonoma County General Plan Parcel Designation 11-15
Figure 12-1: Noise Monitoring Locations 12-3
Figure 12-2: Transmission Route, Short Term-One Third-Octave Frequency Analyses 12-6
Figure 13-1: Sites with Known Hazardous Material Releases 13-6
Figure 15-1: Scenic Road Corridors 15-9
Figure 15-2: Ridges and Hillsides 15-10
Figure 15-3: Photograph Location Index 15-15