

*Southern California Edison*  
**Presidential Substation Project A.08-12-023**

**DATA REQUEST SET Presidential ED-03 (Part 2)**

**To:** CPUC

**Prepared by:** Kristin Kelly

**Title:** Project Manager, Transmission Licensing

**Dated:** 05/19/2009

---

**Question 29:**

**Project Description**

The PEA states that survey crews would survey the limits of grading for structure excavations. Provide information as to what the approximate limits of grading for structure excavation would be for pole installation. There is discussion of situations where excavation may be required for pole removal; include approximate limits of grading for pole removal as well.

**Response to Question 29:**

Temporary grading may need to occur near the pole installation sites in order for cranes and/or trucks to be positioned to install the pole. Approximately 25 feet of temporary working space is needed around each pole site for this type of work. Where needed, permanent clearing and final grade will need to be maintained 10 feet in diameter around each pole site.