

# Proponent's Environmental Assessment (PEA) Checklist for Underground Gas Storage Facilities

#### **TABLE OF CONTENTS**

#### **Executive Summary**

Cover Sheet
Table of Contents
Executive Summary: PEA Summary
Organization of the PEA

#### **Chapter 1: Purpose and Need**

- 1.1 Purpose and Need of the Proposed Project
- 1.2 Purpose and Need for California Natural Gas/Energy Industry
  - 1.2.1 Background
  - 1.2.2 Related Storage Facilities
  - 1.2.3 Project Application

#### **Chapter 2: Project Details**

- 2.1 Project Background
- 2.2 Project Ownership
- 2.3 Site Description
  - 2.3.1 Location
  - 2.3.2 Land Uses and Environmental Setting
  - 2.3.3 Formation Information
- 2.4 Existing Facilities
  - 2.4.1 History of the Oil/Gas Field
  - 2.4.2 Underground Natural Gas Field
  - 2.4.3 Reservoir Development
- 2.5 Existing Operations (if an expansion of existing storage)
  - 2.5.1 Gas Injection Operations (if field expansion)
  - 2.5.2 Withdrawal Operations
  - 2.5.3 Produced Water and other associated products
  - 2.5.4 Cushion Gas Injection
- 2.6 Project Components

Well-head Site(s)

Page 1 of 25 November 2008

Compressor Station

Pipelines and Interconnection with Existing Facilities

Remote Facilities (Metering/Telemetry/Control)

Hazardous Materials Use and Storage

Electric Transmission Lines and Other Utilities

- 2.7 Facility and Route Selection and Evaluation Process
- 2.8 Production Information
- 2.9 Reservoir Information

#### **Chapter 2: Project Description (continued)**

- 2.10 Project Land Requirements
- 2.11 Right-of-Way Requirements
- 2.12 Construction
  - 2.12.1 Staging and Access
  - 2.12.2 Construction Schedule, Work Force, and Equipment
    - 2.12.2.1 Construction Work Force
  - 2.12.3 Construction Method
    - 2.12.3.1 Clearing and Grading
    - 2.12.3.2 Erosion and Sediment Control and Pollution Prevention
    - 2.12.3.3 Construction Components
      - Well Pad/Drilling
      - Gas Pipeline Installation and Isolation
      - Compressor Station
      - ROW Isolation
      - Associated Pipelines
      - Remote Facility Site Metering, Telemetry, Control
      - Gas Processing
      - Interconnections
      - Access Roads
      - ROW Restoration, Cleanup, and Post-Construction Restoration
- 2.13 Operation and Maintenance
- 2.14 Future Plans
- 2.15 Regulatory Requirements
  - 2.15.1 Federal Regulations
  - 2.15.2 State Regulations
  - 2.15.3 Local Requirements
  - 2.15.4 Permit Requirements

#### **Chapter 3: Environmental Setting**

#### **Chapter 4 Environmental Impact Assessment**

- 4.1 Aesthetics
- 4.2 Agricultural Resources
- 4.3 Air Quality
- 4.4 Biological Resources
- 4.5 Cultural Resources
- 4.6 Geology, Soils, and Seismicity

Page 2 of 25 November 2008

- 4.7 Hazards and Hazardous Materials
- 4.8 Hydrology and Water Quality
- 4.9 Land Use and Planning
- 4.10 Mineral Resources
- 4.11 Noise
- 4.12 Population and Housing
- 4.13 Public Services
- 4.14 Recreation
- 4.15 Transportation and Traffic
- 4.16 Utilities and Services Systems
- 4.17 Cumulative Analysis
- 4.18 Growth-Inducing Impacts, if Significant

#### **Chapter 5: Detailed Discussion of Significant Impacts**

- 5.1 Mitigation Measures to Minimize Significant Effects
- 5.2 Growth-Inducing Impacts
- 5.3 Suggested Applicant Proposed Measures to address GHG Emissions

#### **Chapter 6: Alternatives**

- 6.1 Factors used in selecting Alternatives
- 6.2 Alternatives Evaluated in this PEA

#### **List of Tables**

| rable E2-1    | Summary impacts and mitigation measures                |
|---------------|--|
| Table ES-1    | Summary of Alternatives                                |
| Table 2.8.2-1 | Major Construction Phases and Workforce                |
| Table 2.8.2-2 | Construction Schedule                                  |
| Table 2.8.2-3 | Construction Activity, Equipment and Workforce         |
| Table 2.8.2-4 | Construction Equipment Type and Use                    |
| Table 2.8.4-1 | Construction Access Roads – Type, Description, Acreage |

Page 3 of 25 November 2008

### **Executive Summary**

- ☐ Typically from two to ten pages in length (without tables) depending on complexity of the project and the number and significance of the projects impacts.
- □ PEA Executive summary should include, but is not limited to, the following:
  - The primary project components (well-head, compressor station, pipeline connections, etc)
  - The major areas of impact (e.g., air, water, visual, etc.);
  - the major conclusions of the PEA;
  - any areas of controversy;
  - any major issues that must be resolved including the choice among reasonably feasible alternatives and mitigation measures, if any,
  - a list of other state, local and federal permits required; and whether any of these agencies will be resource agencies;
  - a description of interagency coordination, if any; and
  - a description of public outreach efforts, if any.
- ☐ The PEA Executive Summary should also include:
  - PEA organization and one line description of each chapter
  - A summary table of impacts and mitigation measures
  - A summary table of alternatives

Page 4 of 25 November 2008

## Chapter 1: Purpose and Need

This section lists the information necessary under CEQA to describe the objectives and purpose for the Proposed Project, the organization of the PEA and a facility overview.

#### 1.1 Purpose and Need of the Project

| Generally not more than two pages in length, except where significant or potentially significant project impacts have been identified. Explanation of the objective(s) and/or Purpose and Need for implementing the Proposed Project. Analysis of project objectives, purpose and need must be sufficiently detailed to permit the Commission to independently evaluate the project need and benefits in order to accurately consider them in light of the potential environmental impacts. |
|---|
| Describe ways in which the facility has fit/will fit into the dynamics of the natural gas industry and energy demand in California.   |
|   |
|   |

### 1.2 Background

#### 1.2.1 Background

This section will also provide the background on the natural gas formation contributing to the existing natural gas facility.

#### 1.2.2 Related Storage Facilities

#### 1.2.3 Project Application

Describe how existing storage facilities will work in conjunction with the proposed project. Describe the purchasing process (injection, etc) and transportation arrangements this facility will have with its customers.

Page 5 of 25 November 2008

Chapter 2: Project Details

| 2.1 Project Description |
|-------------------------|
|-------------------------|

| Describe the whole of the Proposed Project. Is it an upgrade, an expansion, a new field, new wells or pipelines, etc.   |
|---|
| Describe how the Proposed Project fits into the regional gas system, including interconnection to the regional transmission system, existing storage, and associated pipeline requirements.   |
| Describe all reasonably foreseeable future phases, or other reasonably foreseeable consequences of the Proposed Project.  |
| Provide storage capacity or storage capacity increase in billion cubic feet (bcf). If the project does not increase capacity, state it.   |
| Provide GIS (or equivalent) data layers for the Proposed Project preliminary engineering including estimated locations of all physical components of the Proposed Project as well as those related to construction. For physical components, this could include but is not limited to the existing components (e.g., ROWs, facility locations, wells, pipelines, transmission lines, etc.). For elements related to construction include: proposed or likely laydown areas, work areas, access roads (e.g., temporary, permanent, existing, etc.), areas where special construction methods may need to be employed, areas where vegetation removal may occur, areas to be heavily graded, etc. More details about this type of information are provided below. |

## 2.2 Project Ownership

| Storage facility          |
|---------------------------|
| Wells                     |
| Pipelines                 |
| Transmission line (if any |
| Compressor Station        |

### 2.3 Site Description

#### 2.3.1 Location

☐ Geographical Location: County, City (provide project location map(s)). Show location on a detailed topographic and regional map.

Page 6 of 25 November 2008

|                             | 2.3.2    | <ul> <li>Land Uses and Environmental Setting</li> <li>□ General Description of Land Uses and environmental settings within and adjacent to the location of the project facilities (e.g., residential, commercial, agricultural, recreation, traverses vineyards, farms, open space, number of stream crossings, etc.).</li> <li>□ Describe if the Proposed Project is located within an existing property owned by the Applicant, traverses existing rights of way (ROW) or requires new ROW. Give the approximate area of the property or the length of the project that is in an existing ROW or which requires new ROWs.</li> </ul> |  |  |
|-----------------------------|----------|--|--|--|
| 2.3.3 Formation Information |          |  |  |  |
|                             |          | <ul> <li>□ Depth of new or existing wells</li> <li>□ Description of overlying stratigraphy, especially caps</li> <li>□ Description of production, injection, and intervening strata</li> <li>□ Types of Rock</li> <li>□ Description of types of rocks in formation, including permeability, fractures</li> <li>□ Thickness of Strata</li> <li>□ Provide graphic and/or table showing formation thicknesses</li> <li>□ Identify and describe any potential gas migration pathways, such as faults, permeable contacts, abandoned wells, underground water or other pipelines</li> </ul>   |  |  |
| 2.4                         | Exist    | ting Facilities  |  |  |
| • Pro                       | ovide ov | verview of existing facilities.  |  |  |
|                             | 2.4.1    | <ul> <li>History of the Oil/Gas Field</li> <li>□ First well drilling, production history, abandonment procedures, inspections, etc.</li> </ul>   |  |  |
|                             | 2.4.2    | <ul> <li>Underground Natural Gas Field</li> <li>□ Describe the production zones, including depth, types of formations, characteristics of field</li> <li>□ Provide cross section of the geologic formations and structures.</li> </ul>   |  |  |
|                             | 2.4.3    | <ul> <li>Reservoir Development</li> <li>□ Describe storage capacity and limiting factors, such as injection or withdrawal criteria.</li> <li>□ Describe cushion gas requirements.</li> <li>□ Provide simulation studies that were used to predict the reservoir pressure response under gas injection and withdrawal operations.</li> </ul>  |  |  |
| 2.5 E                       |          | ng Operations<br>e a map showing all existing facilities   |  |  |

Page 7 of 25 November 2008

| <ul><li>2.5.1 Gas Injection Operations (if field expansio</li><li>□ Describe any existing injection wells—completed in (injection formation), injection</li></ul>   | -size, depth, formation the well is   |
|---|---------------------------------------|
| 2.5.2 Withdrawal Operations  ☐ Describe any existing withdrawal or preserved formation the well is completed in (proinformation and withdrawal rates)   | · · · · · · · · · · · · · · · · · · · |
| 2.5.3 Produced Water and other associated produced □ Describe methods for treating produced □ Describe methods for treating other as  | ed water                              |
| 2.5.4 Cushion Gas Injection  ☐ Describe any cushion gas injection—for (cushion gas formation), injection information  |                                       |
| 2.6 Project Components  |                                       |
| Well-Head Site(s)  □ Existing ■ Describe location, depth, size, comp □ Abandoned Wells ■ Describe location, depth, size, comp □ Proposed Production and Injection wells ■ Describe location, depth, size, comp □ Monitoring or Test Wells  Compressor Station □ Describe the compressor station, if needed on the | eletion information                   |
| Pipelines and Interconnections with Existing Fa  ☐ Number ☐ Size ☐ Route • Below Ground installations • Above Ground installations  | acilities                             |
| Remote Facilities  Metering Telemetry Control   |                                       |
| Hazardous Materials Use and Storage   |                                       |
| Electric Transmission and Other Utilities/Facilit  Administrative Office  | ies                                   |

Page 8 of 25 November 2008

|       |   | Non-hazardous Chemical Storage   |
|-------|---|--|
| 2.7   |   | ity Route Selection and Evaluation Process  Describe how the route was determined, what routes were considered and rejected, what sensitive resources were avoided, what factors make this the best route  |
| 2.8   |   | Production and Injection Pressures Production and Injection depths Production and Injection rates Production Injection Cycles - Twenty Four Hour - Weekly - Seasonal   |
| 2.9   |   | ervoir Information Storage Capacity Structure and Cushion Gas requirements   |
| 2.10  |   | Well Pad Site Loop Pipeline Remote Facility Site Connection Pipeline and Interconnect Any other facilities   |
| 2.11  |   | <ul> <li>t-of-Way Requirements</li> <li>Gas Pipeline <ul> <li>Below ground installation</li> <li>Above ground installation</li> </ul> </li> <li>Describe the location, ownership, and width. Would existing ROW be used or would new ROW be required?</li> <li>If new ROW is required, describe how it would be acquired and approximately how much would be required (length and width).</li> <li>List properties likely to require acquisition.</li> </ul> |
| 2.12( |   | truction Staging and Access Well Pad Site Gas Pipeline Compressor Station Interconnect Remote Facility   |
|       | 0 | Construction Staging For all Projects Where would the main staging area(s) likely be located?  |

Page 9 of 25 November 2008

| Ш | Approximately now large would the main staging area(s) be?                       |
|---|--|
|   | Describe any site preparation required, if known, or generally describe what     |
|   | might be required (i.e., vegetation removal, new access road, installation of    |
|   | rock base, cut and fill) etc.).  |
|   | Describe what the staging area would be used for (i.e., material and             |
|   | equipment storage, field office, reporting location for workers, parking area fo |
|   | vehicles and equipment, etc.).   |
|   | Describe how the staging area would be secured, would a fence be installed?      |
|   | If so, describe the type and extent of the fencing.                              |
|   | Describe how power to the site would be provided if required (i.e., tap into     |
|   | existing distribution, use of on-site generators, etc.)                          |
|   | Describe any grading activities and/or slope stabilization issues                |

#### 2.12. 2 Construction Schedule, Work Force, and Equipment

Table 2.12.2-1(Convert following to Gantt chart format)

| Project Activity                                   | Proposed Project<br>(Month Year or<br>Month Year to Month Year) |
|--|---|
| Permit To Construct decision adopted and effective |   |
| Acquisition of required permits                    |   |
| Right-of-way / property acquisition                |   |
| Final engineering completed                        |   |
| Construction begins                                |   |
| Project operational                                |   |
| Clean up   |   |
|  |   |

#### 2.12.2.1 Construction Work Force

[Note: in the absence of project specific data, provide estimates based on past projects of a similar *size* and type.]

| crews at different sites); would they be phased, etc.  Describe the different types of activities to be undertaken during of the number of crew members for each activity i.e. trenching, grad and number and types of equipment expected to be used for said | proje | ects of a similar <i>size</i> and type.j  |
|---|-------|---|
| crews at different sites); would they be phased, etc.  Describe the different types of activities to be undertaken during of the number of crew members for each activity i.e. trenching, grad and number and types of equipment expected to be used for said | _ F   | Provide the estimated number of construction crew members.                      |
| Describe the different types of activities to be undertaken during of<br>the number of crew members for each activity i.e. trenching, grad<br>and number and types of equipment expected to be used for said  |       | Describe the crew deployment, would crews work concurrently (i.e., multiple     |
| the number of crew members for each activity i.e. trenching, grad and number and types of equipment expected to be used for said  | (     | crews at different sites); would they be phased, etc.                           |
| and number and types of equipment expected to be used for said  |       | Describe the different types of activities to be undertaken during construction |
|   | t     | the number of crew members for each activity i.e. trenching, grading, etc.;     |
| Include a written description of the activity. See examples below.  |       | and number and types of equipment expected to be used for said activity.        |
| ,   | I     | Include a written description of the activity. See examples below.              |

Page 10 of 25 November 2008

Table 2.12.2-2: Major Construction Phases and Workforce

| Phase                          | Total<br>Workforce | Nonlocal<br>Workforce | Estimated<br>Duration | Construction<br>Year |
|--------------------------------|--------------------|-----------------------|-----------------------|----------------------|
| Pipeline Construction          | 65                 | 10                    | 32 weeks              | 2003                 |
| Interconnect Facility          | 20                 | 5                     | 18 weeks              | 2003                 |
| Well Pad Expansion             | 20                 | 0                     | 4 weeks               | 2002                 |
| Well Drilling                  | 32                 | 12                    | 16 weeks              | 2003                 |
| Remote Facility Expansion      |                    |                       |                       |                      |
| Site Preparation               | 20                 | 10                    | 4 weeks               | 2002                 |
| Civil                          | 34                 | 13                    | 6 weeks               | 2002/03              |
| Mechanical                     | 42                 | 20                    | 28 weeks              | 2003                 |
| Electrical/<br>Instrumentation | 45                 | 5                     | 34 weeks              | 2003                 |
| Testing/Commissioning          | 15                 | 0                     | 3 weeks               | 2004                 |
| Phase                          | Total<br>Workforce | Nonlocal<br>Workforce | Estimated<br>Duration | Construction<br>Year |
| Clean-up/Restoration           | 10                 | 5                     | 14 weeks              | 2004                 |
| PROJECT TOTALS                 | 303                | 80                    |                       |                      |

Table 2.12.2-3: CONSTRUCTION
ESTIMATED PERSONNEL AND EQUIPMENT

| Activity                        | People | Quantity of Equipment                  |
|---------------------------------|--------|--|
| Survey                          | 3      | 1 pickup truck                         |
| Access Road Construction        | 2-3    | 1 bulldozer (D-8 Cat)                  |
|                                 |        | 1 motor grader                         |
|                                 |        | 1 pickup truck                         |
|                                 |        | 1 water truck (for construction)       |
| Auger Holes, Direct Embed Poles | 5      | 1 hole digger                          |
|                                 |        | 1 backhoe or bucket excavator          |
|                                 |        | 1 water truck                          |
|                                 |        | 1 pickup truck                         |
|                                 |        | 1 line truck                           |
| Material Haul                   | 3      | 1 Tractor Trailer                      |
|                                 |        | 2 yard and field cranes or line trucks |
|                                 |        | 1 fork lift                            |
|                                 |        | 1 truck (2 ton)                        |
|                                 |        |  |
|                                 |        | 1 pickup truck                         |
|                                 |        | 1 bucket buck                          |
|                                 |        | 1 line truck                           |

Page 11 of 25 November 2008

| Well Installation                | 8 |                     |
|----------------------------------|---|---------------------|
|                                  |   | 3 diesel generators |
|                                  |   | 1 Crane             |
|                                  |   | 1 line truck        |
|                                  |   | 3 pick up trucks    |
|                                  |   |                     |
|                                  |   |                     |
|                                  |   | 1 Truck             |
| Right-of-way -ration and Cleanup | 4 | 1 truck             |
|                                  |   | 1 motorgrader       |
|                                  |   | 1 pickup truck      |
|                                  |   | 1 water truck       |

□ Provide a list of the types of equipment expected to be used during construction of the Proposed Project as well as a brief description of the use of the equipment. See example below.

Table 2.12.2-4: EQUIPMENT EXPECTED TO BE USED DURING PROJECT CONSTRUCTION

| Type of Equipment           | Use   |
|-----------------------------|---|
| Truck                       | Lift and Transport workers                                  |
| Crane                       | Erect pole structure, lift and transport heavy construction |
|                             | items   |
| Backhoe or Bucket Excavator | Transport personnel, tools, and materials                   |
| Crew-Cab/Pick-ups           | Pull pole trailer for multi-pole loads                      |
| Diesel Tractor              | Haul material   |
| Fork Lift                   | Road Construction (staging, pull sites)                     |
|                             |   |
| Grooming/Grading Equipment  | Move/compact soils  |
| dozer                       | compaction and dust control                                 |
| water truck                 | to properly pitch road for run-off                          |
| motor grader                | Excavate holes  |
|                             |   |
| Drill Rig                   | Compressors, trailers, tanks, install pole/conductor        |
| Line Truck                  |   |
| Mobile Office               | Supervision and clerical office                             |
| Pullers, Reel Dolly         | Install conductor   |
| Tensioned                   | Install and move conductor                                  |
| Tractor trailer             | Haul Materials  |
| Two-ton truck               | Haul Materials  |
|                             |   |

#### 2.12.3 Construction Methods

#### 2.12.3.1 Clearing and Grading

Page 12 of 25 November 2008

|        | Vegetation Clearance [Note: specific amounts and types of vegetation removed may not be known until plant surveys, field reviews and project engineering are complete. However, the applicant is expected to have a reasonable estimate of the vegetation clearance required for each project based on established data   |
|--------|---|
|        | available for each project area.]  Describe what types of vegetation clearing may be required (e.g., tree removal,  |
|        | brush removal, flammable fuels removal) and why (e.g., to provide access, etc.). Identify the preliminary location and provide an approximate area of disturbance in the GIS database for each type of vegetation removal.  |
|        | Describe how each type of vegetation removal would be accomplished.  Describe the types and approximate number and size of trees that may need to be removed. Describe the type of equipment typically used.  |
| 2.12.3 | .2 Erosion and Sediment Control and Pollution Prevention  |
|        | Describe the areas of soil disturbance including estimated total areas, and associated terrain type and slope. List all known permits required. For project sites of less than one acre, outline the best management practices (BMPs) that would be implemented to manage surface runoff. Things to consider include, but are not limited to, the following: <ul> <li>Erosion and Sedimentation BMP's;</li> <li>Vegetation Removal and Restoration; and/or,</li> <li>Hazardous Waste and Spill Prevention Plans.</li> </ul> |
|        | Describe any grading activities and/or slope stabilization issues.  Describe how construction waste (i.e., refuse, spoils, trash, oil, fuels, etc.) would be disposed.  |
| 2.12.3 | .3 Construction Components  |
|        | Pad Construction  |
|        | Describe construction methods, amount of cut and fill, source of fill (if imported). List construction equipment and schedule for use   |
|        | Orilling  Describe type of drill rig (diesel or electric), depth of well, drilling schedule, ensite   |
|        | Describe type of drill rig (diesel or electric), depth of well, drilling schedule, onsite equipment.  |
|        | List estimated use of drilling muds and other materials, types and quantities.  |
| Comp   | ressor Station  |
|        | ipeline Installation and Isolation enching and Trenchless Techniques, Stringing, Backfilling, Hydrostatic Testing   |
|        | <ul> <li>Trenching</li> <li>□ Describe the approximate dimensions of the trench (e.g., depth, width).</li> <li>□ Describe the methodology of making the trench (e.g., saw cutter to cut the pavement, back hoe to remove, etc.).</li> </ul>   |

Page 13 of 25 November 2008

| Ш   | the trench, the amount to be used as backfill and the amount to subsequently   |
|-----|--|
|     | be removed disposed of offsite.  Provide off-site disposal location, if known, or describe possible option(s).  If engineered fill would be used as backfill, provide information as to the type of engineered backfill and the amount that would be typically used (e.g., the top two feet would be filled with thermal-select backfill). |
|     | Describe if dewatering would be anticipated, if <i>so,</i> how the bench would be dewatered, what are the anticipated flows of the water, would there be treatment, and how would the water be disposed.   |
|     | <ul> <li>Describe the process for testing excavated soil or groundwater for the<br/>presence of preexisting environmental contaminants that could be<br/>exposed as a result of trenching operations.</li> </ul>   |
|     | <ul> <li>If a preexisting hazardous waste were encountered, describe the process of removal and disposal.</li> <li>Describe any standard PMPs that would be implemented.</li> </ul>  |
|     | <ul> <li>Describe any standard BMPs that would be implemented.</li> </ul>  |
|     | enchless Techniques: Microtunnel, Bore and Jack, Horizontal Directional  |
|     | lling Provide the approximate location of the sending and receiving pits. Provide the length, width and depth of the sending and receiving pits. Describe the methodology of excavating and shoring the pits. Describe the methodology of the trenchless technique.  |
|     | Provide the total cubic yardage of material to be removed from the pits, the amount to be used as backfill and the amount to subsequently be removed/disposed of off-site.   |
|     | Describe process for safe handling of drilling mud and bore lubricants.  Describe process for detecting and avoiding "fracturing-out" during HDD operations.   |
|     | Describe process for avoiding contact between drilling mud/lubricants and stream beds.   |
|     | If engineered fill would be used as backfill, provide information as to the type of engineered backfill and the amount that would be typically used (e.g., the top two feet would be filled with thermal-select backfill).   |
|     | Describe if dewatering would be anticipated, if so, how the pit would be dewatered, what are the anticipated flows of the water, would <i>there</i> be treatment, and how would the water be disposed.   |
|     | Provide the number of and describe stream crossings that will occur during trenching, the method of trenching through stream crossings, and the process for avoiding impacts to streams required for pipeline construction.  |
|     | Describe the process for testing excavated soil or groundwater for the presence of preexisting environmental contaminants.   |
|     | If a preexisting hazardous waste were encountered, describe the process of removal and disposal.   |
|     | Describe any grading activities and/or slope stabilization issues.  Describe any standard BMPs that would be implemented.  |
| Str | ringing Describe method for pipe stringing.  |

Page 14 of 25 November 2008

|                  |  | tion<br>ethods for pipeline installation, inclepths, and widths.   | uding clearing, grading,   |
|------------------|--|--|--|
|                  | Backfilling ☐ Describe me open trenche   | ethods for backfilling, including stoes.   | ckpiling topsoil and timing of   |
|                  | flushing water Describe en   | sting drostatic testing process including er, discharge of water. ergy dissipation basin, size of seg launching locations, if applicable.  | ments to be tested.  |
| Assoc            | iated Pipelines  |  |  |
|                  | Describe constr  | uction methods, locations, right-of-<br>ctional drilling, stream crossing, ed  |  |
| Dight            | of-way Isolation   |  |  |
|                  | •  | ds to isolate the ROW if necessary   | y, including culverts and water  |
| Pemoi            | e Facility Site  |  |  |
|                  |  |  | operation of the facility.   |
| Interce          | onnections   |  |  |
| Acces            | s Roads  |  |  |
|                  | Describe the type<br>to implement the<br>information requested permanent road<br>improvements; of<br>paved road; exist | pes of roads that would be used and Proposed Project. See table belowed. Road types may include, but the include, but the include, but the include include, but the include in | ow as an example of are not limited to: new ad that would have permanent porary improvements, existing access. |
|                  |  | hat require preparation, describe t  | he methods and equipment   |
| _                | that would be us   |  |  |
|                  |  | nate location of all access roads (l<br>cess Road Requirements.  | by type) in the GIS database.  |
|                  |  | ading activities and/or slope stabil   | ization issues.  |
|                  |  |  |  |
| Access Road      | S  |  |  |
| Type of Road     | - 1  | Description  | Area Proposed Project  |
| Existing Dirt Ro | aa   | Typically double track. <i>May</i> have been graded previously. No other   | acres  |
|                  |  | preparation required, although a   |  |
|                  |  | few sections may need to be re-  |  |

Page 15 of 25 November 2008

|                 | graded and crushed rock applied in very limited areas for traction.   |       |
|-----------------|---|-------|
| New Permanent   | Would be xx feet wide, bladed. No other preparation required although crushed rock may need to be applied in very limited areas for traction. | acres |
| Overland Access | No preparation required. Typically grassy areas that are relatively flat. No restoration would be necessary.                                  | acres |

|  | Describe methods for | or restoring | excavated ROW, | re-vegetation, | etc. |
|--|----------------------|--------------|----------------|----------------|------|
|--|----------------------|--------------|----------------|----------------|------|

- ☐ Describe how cleanup and post-construction restoration would be performed (i.e., personnel, equipment, and methods). Things to consider include, but are not limited to, restoration of the following:
  - Natural drainage patterns

**Pipeline Inspections** 

- Wetlands;
- Vegetation; and
- Other disturbed areas (i.e. staging areas, access roads, etc.).

#### 2.13 Operation and Maintenance

- □ Describe the general system monitoring and control (i.e., use of standard monitoring protection equipment, pressure sensors, automatic shut-off valves, etc.).
  - Describe the general maintenance program of the Proposed Project, include items such as: Timing of the inspections (i.e., monthly, every July, as needed);
  - Type of inspection (i.e., aerial inspection, ground inspection); and
  - Description of how the inspection would be implemented. Things to consider, who/how many crew members; how would they access the site (walk to site, vehicle, ATV); would new access be required; would restoration be required, etc.

| restoration be required, etc.  |
|--|
| If additional full time staff would be required for operation and/or maintenance |
| provide the number and for what purpose.   |
| General system monitoring and control  |
| Well pad site monitoring and control   |
| Remote Facility Site Monitoring and Control Systems                              |
| Control Room Technology  |
| Equipment Operation  |
| Facility Inspection and Survey   |
|  |

Page 16 of 25 November 2008

|                     | <ul> <li>Well Pad Site Inspections</li> <li>Remote Facility Site Inspections</li> <li>Number of inspections, number of trips, facilities inspected.</li> <li>Maintenance and Repair Procedures</li> <li>Scheduled Site Maintenance</li> <li>Parts and Materials</li> <li>Ongoing General Maintenance</li> <li>Vegetation Management</li> <li>Access Road maintenance</li> <li>Electric Test System Installation</li> <li>Cathodic Protection</li> <li>Pipeline Replacement</li> <li>Well Work-over</li> <li>Gas Storage</li> <li>Pigging Activities</li> <li>Gas Storage</li> <li>Wells</li> <li>Pipeline</li> </ul> |
|---------------------|--|
| <b>2.14 Futur</b> □ | e Plants Abandonment   |
|                     | Expansion  |
| <b>2.15.1</b>       | latory Requirements Federal Regulations U.S. Department of Transportation – Office of Pipeline Safety U.S. Environmental Protection Agency Resource Conservation and Recovery Act (RCRA) Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)  |
|                     | State Regulations California Division of Oil, Gas and Geothermal Resources (DOGGR) California Regional Water Quality Control Board (RWQCB) – Regional National Pollutant Discharge Elimination System General Industrial Storm Water Discharge Permit California Environmental Protection Agency – Department of Toxic Substances Control Hazardous Materials Release Response Plan and Inventory Act of 1985 Hazardous Waste Control Act California State lands Commission (SLC) Office of State Fire Marshall  |
|                     | Local Regulations Cities and Counties  |
|                     | Permitting Requirements of Applicable Regulated agencies Federal, state, and local   |

Page 17 of 25 November 2008

### Chapter 3: Environmental Setting

Note: The discussion of Environmental Setting may be combined within each resource area in the Environmental Assessment Summary.

- ☐ For each resource area discussion, the PEA must include the following:
  - A description of the physical environment in the vicinity of the project (e.g. topography, land use patterns, biological environment, etc.)
    - local environment (site-specific)
    - regional environment
  - A description of the regulatory environment/context
    - Federal
    - State
    - Local
- ☐ Detailed descriptions should be limited to those resource areas which may be subject to a potentially significant impact.

Page 18 of 25 November 2008

# Chapter 4: Environmental Impact Assessment Summary All impacts identified as significant or potentially significant must be explained in detail in accord

| with Chapter 5      | 5 criteria  |
|---------------------|---|
| <b>4.1 Aesthe</b> □ | Provide visual simulations of prominent public view locations, including scenic highways to demonstrate the before and after project implementation. Additional simulations of affected private view locations are highly recommended.                      |
|                     | Iture Resources Identify the types of agricultural resources affected.  |
| 4.3 Air Qua         | Provide supporting calculations / spreadsheets / technical reports that support construction and operation emission estimates in the PEA.   |
|                     | Provide documentation of the location and types of sensitive receptors that could be impacted by the project ( <i>e.g.</i> , schools, hospitals, houses, etc.). Critical distances to receptors is dependent on type of construction activity.              |
|                     | Quantify project greenhouse gas (GHG) emissions.  |
|                     | The assessment of air quality impacts must be consistent with the area and the conditions of the local environment described in PEA Chapter 3 as well as with the PEA's analysis of impacts during construction, including traffic and all other emissions. |
| •                   | ical Resources<br>an impacts analysis:  |
|                     | Provide location of the wetland area  |
|                     | Provide a copy of special status surveys for wildlife, botanical and aquatic species, as applicable. Any GIS data documenting locations of special-status species should be provided.   |
|                     | al Resources<br>an Impacts Analysis:  |
|                     | Cultural Resources Report documenting a cultural resources investigation of the   |

Page 19 of 25 November 2008

survey, and Native American consultation.

Proposed Project. This report should include a literature search, pedestrian

|                            |      | Describe the potential for encountering human remains or grave goods during the trenching or any other phase of construction.   |
|----------------------------|------|---|
|                            |      | Describe measures that would be taken in the result of undiscovered artifacts or human remains.   |
|                            |      | Provide a copy of the records found in the literature search.   |
|                            |      | Provide a copy of all letters and documentation of Native American consultation.  |
|                            | _    | gy, Soils, and Seismic Potential an impacts analysis:   |
|                            |      | Provide a copy of geotechnical investigation if completed, including known and potential geologic hazards such as ground shaking, subsidence, liquefaction, etc.  |
| <b>4.7 Haz</b> a<br>apply] | ard  | Is and Hazardous Materials [Note: reference and list the documents that   |
|                            |      | Describe potential for and effects of gas migration through natural and manmade   |
|                            |      | pathways.  Describe mitigation measures for avoiding gas emissions at the surface from gas  |
|                            |      | migration pathways.  Describe mitigation measures for avoiding emissions of mercaptin and/or other odorizing agents.  |
| In addition                | to a | an impacts analysis:  |
|                            |      | Environmental Data Resources report. Hazardous Substance Control and Emergency Response Plan. Health and Safety Plan. Worker Environmental Awareness Program (WEAP). Describe what chemicals would be used during construction and operation of the Proposed Project. For example: fuels, etc. for construction, naphthalene to treat wood poles before installation. |
| In addition                | to a | an impacts analysis:  |
|                            |      | Environmental Data Resources report.  |
|                            |      | Hazardous Substance Control and Emergency Response Plan.  |
|                            |      | Health and Safety Plan, including a plan for addressing gas leaks, fires, etc. Identify sensitive receptors, methods of evacuation, protection measures.  |
|                            |      | Health Risk Assessment, including risk from potential gas leaks, fires, etc. Identify sensitive receptors that would be affected and potential impacts on them if there is a gas release.   |
|                            |      | Worker Environmental Awareness Program (WEAP).  |

Page 20 of 25 November 2008

| Describe what chemicals would be used during construction and operation of the    |
|---|
| Proposed Project. For example: fuels, etc. for construction, naphthalene to treat |
| wood poles before installation.   |

#### 4.8 Hydrology and Water Quality

In addition to an impacts analysis:

| Describe impacts to groundwater quality including increased run-off due to construction of impermeable surfaces, etc.  |
|--|
| Describe impact to wetlands, particularly from directional boring  |
| Describe impacts to rivers and streams if a river or stream crossing is required.  |
| Describe impacts to surface water quality including the potential for accelerated soil erosion, downstream sedimentation, and reduced surface water quality. |

#### 4.9 Land Use and Planning

In addition to an impacts analysis, provide GIS data of all parcels within 300' of the Proposed Project with the following data: APN number, mailing address, and parcel's physical address.

#### 4.10 Mineral Resources

Data needs already specified under Chapter 3 would generally meet the data needs for this resource area.

#### **4.11 Noise**

Provide long term noise estimates for operational noise.

### 4.12 Population and Housing

Data needs already specified under Chapter 3 would generally meet the data needs for this resource area.

#### 4.13 Public Services

Data needs already specified under Chapter 3 would generally meet the data needs for this resource area.

#### 4.14 Recreation

Data needs already specified under Chapter 3 would generally meet the data needs for this resource area.

| 4.15 Transportation and <sup>r</sup> | Traffic [Note: the traffic impact assessments should be |
|--------------------------------------|---|
| based on likely or probable routes   | 5.]   |

| Discuss traffic impacts resulting from construction of the Proposed Project including | ongoing |
|---|---------|
| maintenance operations.   |         |

☐ Provide a preliminary description of the traffic management plan that would be implemented during construction of the Proposed Project.

Page 21 of 25 November 2008

# **4.16 Utilities and Services Systems**☐ Describe the existing utilities in the area, including the subsurface lines that could be

| affected by pipeline construction and excavation.   |
|---|
| Identify the sources of water for hydrostatic testing.  |
| Describe method of disposing of testing water.  |
| Cumulative Analysis  Provide a list of projects (i.e., past, present and reasonably foreseeable future projects) within the Project Area in which that the applicant is involved. |
| Provide a list of projects that have the potential to be proximate in space and time to the   |

#### 4.18 Growth-Inducing Impacts, If Significant

planning agency, Caltrans, etc.

- ☐ Provide information on the Proposed Project's growth inducing impacts, if any. The information should include, but is not necessarily limited, to the following:
  - Any economic or population growth, in the surrounding environment that will directly or indirectly, result from the Proposed Project.

Proposed Project. Agencies to be contacted including, but are not limited to: the local

- Any increase in population that could further tax existing community service facilities (i.e., schools, hospitals, fire, police, etc.), that will directly or indirectly result from the Proposed Project.
- Any obstacles to population growth that the Proposed Project would remove.
- Any other activities, directly or indirectly encouraged or facilitated by the Proposed Project that would cause population growth that could significantly affect the environment, either individually or cumulatively.

Page 22 of 25 November 2008

# Chapter 5: Detailed Discussion of Significant Impacts

#### 5.1 Mitigation Measures

- Please describe measures that will be used to minimize significant impacts
  described in Chapter 4. Also include measures to mitigate inefficient and
  unnecessary consumption of energy (e.g. buffer gas requirements that
  offset the economic/energy efficiency gains contributed by this project).
  Include, if they exist, other measures that are not included but could
  reasonably be expected to reduce adverse impacts.
- Identify the acceptable levels to which such impacts will be reduced and the basis upon which such level were identified (see CEQA Information and Criteria List, Section 14A for more details).
- Please provide in this section a treatment plan in accordance with all state and federal laws for addressing unanticipated human remains or grave goods that may be encountered during trenching for pipelines.

#### 5.2 Growth-Inducing Impacts

#### 5.3 Suggested Applicant Proposed Measures to address GHG Emissions

- ☐ The following are suggested methods to reduce project GHG emissions. These methods were developed with feedback from previous applicants. Applicants can and are encouraged to propose other GHG-reducing mitigations. On-site and/or proximate mitigation measures are encouraged. Off-site mitigations are considered 'mitigations' only when they are performed within California. This list will be updated periodically as better information and performance are obtained.
  - 1. If suitable park-and-ride facilities are available in the Project vicinity, construction workers will be encouraged to carpool to the job site to the extent feasible. The ability to develop an effective carpool program for the Proposed Project would depend upon the proximity of carpool facilities to the job site, the geographical commute departure points of construction workers, and the extent to which carpooling would not adversely affect worker show-up time and the Project's construction schedule.
  - 2. To the extent feasible, unnecessary construction vehicle and idling time will be minimized. The ability to limit construction vehicle idling time is dependent upon the sequence of construction activities and when and where vehicles are needed or staged. Certain vehicles, such as large diesel powered vehicles, have extended warm-up times following start-up that limit their availability for use following startup. Where such diesel powered vehicles are required for repetitive construction tasks, these vehicles may require more idling time. The Proposed Project will apply a "common sense" approach to vehicle use; if a vehicle is not required for use immediately or continuously for construction activities, its engine will be shut off. Construction foremen will include briefings to crews on vehicle

Page 23 of 25 November 2008

use as part of pre-construction conferences. Those briefings will include discussion of a "common sense" approach to vehicle use.

- 3. Use low-emission construction equipment. Maintain construction equipment per manufacturing specifications and use low-emission equipment described here. All off-road construction diesel engines not registered under the CARB Statewide Portable Equipment Registration Program shall meet at a minimum the Tier 2 California Emission Standards for Off-Road Compression-Ignition Engines as specified in California Code of Regulations, Title 13, Sec. 2423(b)(1).
- 4. Diesel Anti-Idling: In July 2004, the CARB adopted a measure to limit diesel-fueled commercial motor vehicle idling.
- 5. Alternative Fuels: CARB would develop regulations to require the use of 1 to 4 percent biodiesel displacement of California diesel fuel.
- 6. Alternative Fuels: Ethanol, increased use of ethanol fuel
- 7. Green Buildings Initiative
- 8. Facility-wide energy efficiency audit.
- 9. Complete greenhouse gas emissions audit. The audit will include a review of the greenhouse gases emitted from those facilities (substations), including carbon dioxide, methane, CFC and HFC compounds, (SF6).
- 10. There is an EPA approved SF6 emissions protocol. http://www.epa.gov/electricpower-sf6/resources/index.html#three
- 11. SF6 program wide inventory. For substations keep inventory of leakage rates.
- 12. Increase replacement of breakers once leakage rates exceed 1% within 30 days of detection.
- 13. Increased investment in current programs that can be verified as being in addition to what the utility is already doing.
- 14. The SF6 Emission Reduction Partnership for the Electric Power Systems was launched in 1999 and currently includes 57 electric utilities and local governments across the U.S. SF6 is used by this industry in a variety of applications, including that of dielectric insulating material in electrical transmission and distribution equipment such as circuit breakers. Electric power systems that join the Partnership must, within 18 months, establish an emission reduction goal reflecting technically and economically feasible opportunities within their company. They also agree to, within the constraints of economic and technical feasibility, estimate their emissions of SF6, establish a strategy for replacing older, leakier pieces of equipment, implement SF6 recycling, establish and apply proper handling techniques, and report annual emissions to EPA.EPA works as a clearinghouse for technical information, works to obtain commitments

Page 24 of 25 November 2008

from all electric power system operators and will be sponsoring an international conference in 2000 on SF6 emission reductions.

- 15. Quantify what comes into the system and track programmatically SF6.
- 16. Applicant can propose other GHG reducing mitigations.

## Chapter 6: Alternatives

- ☐ In accordance with the CPUC CEQA Information and Criteria List, describe all reasonable alternatives to the project or the location of the project, and the factors used in their selection.
  - Describe alternative reservoirs considered for gas storage, including location of field, potential storage, suction gas requirements and location to regional pipelines, roads, and utilities.
  - Describe alternative well-head sites
  - Describe alternative drilling sites
  - Describe alternative pipeline alignments
  - Describe alternative compressor station sites

☐ Describe the No Project Alternative

Page 25 of 25 November 2008