

Appendix C

Air Quality

Organization of Appendix C

A number of revisions were made to the air quality calculations presented in the Proponent's Environmental Assessment. This appendix provides the basis for each revision and presents the revised tables that were used in place of tables presented in Appendix F-1 of the PEA.

Localized Significance Thresholds

The LST analysis presented in the PEA normalized emission rates for construction of transmission lines and subtransmission lines assuming that 500 meters (0.31 miles) of activity would impact one receptor. This value was then divided by the total length of the transmission lines (11.7 miles) to get an adjustment factor of 0.02. The maximum daily emissions were then multiplied by 0.02 to 'normalize' for the amount of construction that would occur over one day. Adjusting the maximum daily emissions by a factor of 0.02 does not represent a conservative analysis since the emissions rates are already adjusted to represent a maximum daily emission rate. Since the entire length of the transmission line will not be constructed over one day, adjusting the daily emissions by a factor of 0.02 is not appropriate.

Furthermore, the LST analysis presented in the PEA did not adjust daily emission rates to represent 'on-site' emissions only. This represents an overly-conservative analysis for substation construction activities.

Table C-1 presents the revised LST analysis that is presented in this DEIR. These emission rates are adjusted to represent on-site emissions only. Therefore, fugitive dust emissions from travel on paved and unpaved roads and worker vehicle emissions were not included. However, mass grading emissions from substation improvement activities were included since these emissions will be generated on-site. The bulk of on-site emissions results from operation of heavy duty construction equipment on the project site.

Table C-1 also presents revised LST mass rate thresholds based on the new state ambient air quality standard of 0.18 ppm for NO_x. The original LST mass rate threshold was developed based on the ambient air quality standard of 0.25 ppm, and is therefore no longer applicable.

Maximum Daily Emissions

Changes described in this appendix resulted in new maximum daily emission rates from a number of activities. Tables C-2 and C-3 show the revised maximum daily combined emissions and maximum daily emissions from each project component respectively. Also, in Appendix F-1 of the PEA the maximum daily PM_{2.5} exhaust emissions from on-site vehicles were calculated based on the assumption that 20.8 percent of exhaust PM₁₀ is less than 2.5 microns in diameter. The SCAQMD suggests that approximately 92 percent of all PM₁₀ generated during diesel fuel combustion is less than 2.5 microns in diameter, thus the PM_{2.5} emission rates from on-site vehicles were adjusted to reflect this fraction (SCAQMD, 2006). Table C-4 presents a revised summary table of fugitive emissions based on changes to paved and unpaved emission rates described in this appendix.

Mass Grading Emission Factor for Substation Grading

Fugitive dust emissions from site grading were estimated in the PEA using the AP-42 emission factor of 80 pounds per acre per day. The AP-42 section that provides this emission factor warns that the factor represents total suspended particulate (TSP) matter generated during mass grading (not necessarily particulate matter less than 10 microns in diameter). The SCAQMD suggests that approximately 48.9 percent of TSP generated during grading activities is 10 microns or less in diameter (PM₁₀) and that 20.8 percent of this PM₁₀ is less than 2.5 microns in diameter (PM_{2.5}) (SCAQMD, 2006). Therefore, the emission factor was adjusted to 39 pounds of PM₁₀ per acre per day and 8 pounds of PM_{2.5} per acre per day. Revised emissions from substation grading are presented in Table C-5. This table also includes a summary of revised fugitive emission rates from travel on unpaved roads during substation construction activities.

Unpaved Road Emission Factors

Fugitive dust emission rates from travel on unpaved roads were estimated in the PEA assuming a 60 percent control efficiency from watering roads twice per day. The SCAQMD recommends a control efficiency of 55 percent for watering of unpaved roads (SCAQMD, 2008a). Table C-6 shows revised emission rates from travel on unpaved roads assuming 55 percent control efficiency rather than 60 percent control efficiency.

Paved Road Emission Factors

For control of fugitive emissions from travel on paved roads, the SCAQMD recommends a control efficiency of 16% for local streets and 26% for arterial/collector streets from street sweeping (SCAQMD, 2008b) while the PEA appendix assumes 60% control for heavy duty truck travel per the 1993 SCAQMD CEQA guidance. Table C-7 shows the corrected emission factor for heavy duty truck travel on paved roads while Table C-8 presents the adjusted emission rates from travel on paved roads based on the adjusted emission factor.

References

- South Coast Air Quality Management District (SCAQMD), 2006. *Final Methodology to Calculate PM_{2.5} and PM_{2.5} Significance Thresholds, Appendix A – Updated CEIDARS Table with PM_{2.5} Fractions*, October 2006.
- SCAQMD, 2008a. *Table XI-D: Mitigation Measure Examples: Fugitive Dust Emissions from Unpaved Roads*, Accessed online (<http://www.aqmd.gov/CEQA/handbook/mitigation/fugitive/TableXI-D.doc>) July 14, 2008.
- SCAQMD, 2008b. *Table XI-C: Mitigation Measure Examples: Fugitive Dust Emissions from Paved Roads*, Accessed online (<http://www.aqmd.gov/CEQA/handbook/mitigation/fugitive/TableXI-C.doc>) July 14, 2008.

Table C-1. Localized Significance Thresholds Analysis
 (Replaces Table F-1 of PEA Appendix F1)

Localized Significance Threshold (lb/day)				
Distance to Receptor	NO _x ^a	CO	PM ₁₀	PM _{2.5}
25	117	845	4	3
50	120	1,328	13	6
100	210	2,422	35	10
250	332	5,687	80	24
500	647	23,061	214	105

^a Thresholds for NO_x have been adjusted based on revised 1 hour state ambient air quality standard of 0.18 ppm.

Construction Emissions (lb/day) ¹					
Phase	Distance to Receptor	Maximum Daily Onsite Emissions ²			
	(m)	CO	NO _x	PM ₁₀	PM _{2.5}
Transmission Line	25	69.1	143.3	14.8	6.9
Subtransmission Line	25	78.5	230.9	17.6	9.4
Devers Substation Construction	250	21.5	44.8	2.6	2.2
Mirage Substation Construction	50	52.0	119.6	21.6	8.8
Concho Substation Construction	20	2.1	4.1	0.2	0.2
Indian Wells Substation Construction	35	2.1	4.1	0.2	0.2
Santa Rosa Construction	40	2.1	4.1	0.2	0.2
Eisenhower Substation Construction	50	23.7	51.3	3.0	2.5
Farrell Substation Construction	24	23.7	51.3	3.5	2.6
Garnet Substation Construction	25	2.1	4.1	0.2	0.2
Thornhill Substation Construction	10	2.1	4.1	0.2	0.2
Tamarisk Substation Construction	10	17.9	34.1	2.7	0.2
Telecommunications	30	20.4	62.3	3.0	2.7

¹ Values above the LSTs are shown in **BOLD**.

² Values include onsite emissions only (worker trips and fugitive dust from paved and unpaved roads were not included).

Table C-2. Maximum Daily Combined Emissions Summary
(Replaces Table F-2 of PEA Appendix F1)

Quarter	Construction Phases Occurring Simultaneously	Combined Maximum Daily Emissions (lbs/day)					
		CO	NOx	ROG	SOx	PM10	PM2.5
2nd Quarter, 2010	Subtransmission Line (Mirage-Santa Rosa)	103.3	233.5	22.6	0.3	246.2	57.4
3rd Quarter, 2010	Mirage Substation Construction, Devers Substation Construction, Eisenhower Substation Construction	115.6	217.6	26.6	0.2	52.4	18.9
3rd Quarter, 2010	Mirage Substation Construction, Devers Substation Construction, Eisenhower Substation Construction, Subtransmission Line (Mirage-Santa Rosa-Tamarisk)	218.9	451.1	49.2	0.5	298.6	76.2
3rd Quarter, 2010	Mirage Substation Construction, Concho Substation Construction, Eisenhower Substation Construction, Subtransmission Line (Mirage-Santa Rosa-Tamarisk)	197.4	410.2	44.1	0.5	283.6	71.6
4th Quarter, 2010	Mirage Substation Construction, Concho Substation Construction, Farrell Substation Construction, Subtransmission Line (Mirage-Santa Rosa-Tamarisk)	197.4	410.2	44.1	0.5	284.0	71.7
1st Quarter, 2011	Mirage Substation Construction, Indian Wells Substation Construction, Farrell Substation Construction, Subtransmission Line (Mirage-Devers-Capwind-Tamarisk)	197.4	410.2	44.1	0.5	284.0	71.7
1st Quarter, 2011	Mirage Substation Construction, Indian Wells Substation Construction, Thornhill Substation Construction, Subtransmission Line (Mirage-Devers-Capwind-Tamarisk)	173.8	362.8	38.3	0.4	272.4	67.5
1st Quarter, 2011	Mirage Substation Construction, Indian Wells Substation Construction, Thornhill Substation Construction, Subtransmission Line (Mirage-Devers-Capwind-Tamarisk)	173.8	362.8	38.3	0.4	272.4	67.5
1st Quarter, 2011	Mirage Substation Construction, Santa Rosa Substation Construction, Thornhill Substation Construction, Subtransmission Line (Mirage-Devers-Capwind-Tamarisk)	173.8	362.8	38.3	0.4	272.4	67.5
1st Quarter, 2011	Mirage Substation Construction, Santa Rosa Substation Construction, Thornhill Substation Construction, Subtransmission Line (Mirage-Concho)	173.8	362.8	38.3	0.4	272.4	67.5
2nd Quarter, 2011	Mirage Substation Construction, Santa Rosa Substation Construction, Tamarisk Substation Construction, Subtransmission Line (Mirage-Concho)	190.6	392.9	42.2	0.4	269.9	68.1
2nd Quarter, 2011	Mirage Substation Construction, Garnet Substation Construction, Tamarisk Substation Construction, Subtransmission Line (Mirage-Concho)	190.6	392.9	42.2	0.4	274.1	69.0
2nd Quarter, 2011	Mirage Substation Construction, Garnet Substation Construction, Tamarisk Substation Construction, Transmission Line (Devers-Mirage #2)	162.8	303.4	33.7	1.7	172.9	45.6
2nd Quarter, 2011	Transmission Line (Devers-Mirage #2, Coachella Valley-Mirage)	75.5	144.0	14.0	1.5	144.9	34.0

Table C-3. Maximum Daily Emissions Per Construction Phase
(Replaces Table F-3 of PEA Appendix F1)

Phase	Emissions (lbs/day)					
	CO	NOx	ROG	SOx	PM10	PM2.5
Transmission Line Loop-In						
Fugitive Dust	0.00	0.00	0.00	0.00	137.85	27.53
On-site vehicle Exhaust	69.14	143.32	13.40	1.54	7.04	6.48
Employee Vehicles	6.33	0.66	0.65	0.01	0.05	0.03
<i>Total</i>	<i>75.47</i>	<i>143.99</i>	<i>14.04</i>	<i>1.55</i>	<i>144.94</i>	<i>34.03</i>
Subtransmission Line						
Fugitive Dust	0.00	0.00	0.00	0.00	236.14	48.20
On-site vehicle Exhaust	78.53	230.94	20.06	0.24	9.84	9.05
Employee Vehicles	24.79	2.59	2.54	0.03	0.20	0.12
<i>Total</i>	<i>103.32</i>	<i>233.53</i>	<i>22.59</i>	<i>0.27</i>	<i>246.18</i>	<i>57.37</i>
Devers Substation Construction						
Fugitive Dust	0.00	0.00	0.00	0.00	12.85	2.73
On-site vehicle Exhaust	21.48	44.77	5.21	0.05	2.26	2.08
Employee Vehicles	3.16	0.33	0.32	0.00	0.03	0.02
<i>Total</i>	<i>24.64</i>	<i>45.10</i>	<i>5.54</i>	<i>0.05</i>	<i>15.14</i>	<i>4.83</i>
Mirage Substation Construction						
Fugitive Dust	0.00	0.00	0.00	0.00	15.52	3.23
On-site vehicle Exhaust	51.96	119.57	13.43	0.12	6.05	5.57
Employee Vehicles	12.13	1.27	1.24	0.01	0.10	0.06
<i>Total</i>	<i>64.10</i>	<i>120.84</i>	<i>14.67</i>	<i>0.13</i>	<i>21.67</i>	<i>8.85</i>
Concho Substation Construction						
Fugitive Dust	0.00	0.00	0.00	0.00	0.00	0.00
On-site vehicle Exhaust	2.13	4.10	0.39	0.00	0.18	0.17
Employee Vehicles	1.05	0.11	0.11	0.00	0.01	0.01
<i>Total</i>	<i>3.19</i>	<i>4.21</i>	<i>0.50</i>	<i>0.01</i>	<i>0.19</i>	<i>0.18</i>
Indian Wells Substation Construction						
Fugitive Dust	0.00	0.00	0.00	0.00	0.00	0.00
On-site vehicle Exhaust	2.13	4.10	0.39	0.00	0.18	0.17
Employee Vehicles	1.05	0.11	0.11	0.00	0.01	0.01
<i>Total</i>	<i>3.19</i>	<i>4.21</i>	<i>0.50</i>	<i>0.01</i>	<i>0.19</i>	<i>0.18</i>
Santa Rosa Substation Construction						
Fugitive Dust	0.00	0.00	0.00	0.00	0.00	0.00
On-site vehicle Exhaust	2.13	4.10	0.39	0.00	0.18	0.17
Employee Vehicles	1.05	0.11	0.11	0.00	0.01	0.01
<i>Total</i>	<i>3.19</i>	<i>4.21</i>	<i>0.50</i>	<i>0.01</i>	<i>0.19</i>	<i>0.18</i>
Eisenhower Substation Construction						
Fugitive Dust	0.00	0.00	0.00	0.00	12.90	2.74
On-site vehicle Exhaust	23.66	51.30	6.05	0.05	2.64	2.43
Employee Vehicles	3.16	0.33	0.32	0.00	0.03	0.02
<i>Total</i>	<i>26.82</i>	<i>51.63</i>	<i>6.38</i>	<i>0.06</i>	<i>15.57</i>	<i>5.19</i>
Farrell Substation Construction						
Fugitive Dust	0.00	0.00	0.00	0.00	13.32	2.82
On-site vehicle Exhaust	23.66	51.30	6.05	0.05	2.64	2.43
Employee Vehicles	3.16	0.33	0.32	0.00	0.03	0.02
<i>Total</i>	<i>26.82</i>	<i>51.63</i>	<i>6.38</i>	<i>0.06</i>	<i>15.99</i>	<i>5.27</i>

Phase		Emissions (lbs/day)					
		CO	NOx	ROG	SOx	PM10	PM2.5
Garnet Substation Construction							
	Fugitive Dust	0.00	0.00	0.00	0.00	4.19	0.90
	On-site vehicle Exhaust	2.13	4.10	0.39	0.00	0.18	0.17
	Employee Vehicles	1.05	0.11	0.11	0.00	0.01	0.01
	<i>Total</i>	<i>3.19</i>	<i>4.21</i>	<i>0.50</i>	<i>0.01</i>	<i>4.38</i>	<i>1.08</i>
Thornhill Substation Construction							
	Fugitive Dust	0.00	0.00	0.00	0.00	4.19	0.90
	On-site vehicle Exhaust	2.13	4.10	0.39	0.00	0.18	0.17
	Employee Vehicles	1.05	0.11	0.11	0.00	0.01	0.01
	<i>Total</i>	<i>3.19</i>	<i>4.21</i>	<i>0.50</i>	<i>0.01</i>	<i>4.38</i>	<i>1.08</i>
Tamarisk Substation Construction							
	Fugitive Dust	0.00	0.00	0.00	0.00	0.06	0.01
	On-site vehicle Exhaust	17.88	34.10	4.24	0.04	1.79	1.65
	Employee Vehicles	2.11	0.22	0.22	0.00	0.02	0.01
	<i>Total</i>	<i>19.99</i>	<i>34.32</i>	<i>4.46</i>	<i>0.04</i>	<i>1.87</i>	<i>1.67</i>
Telecommunications Line							
	Fugitive Dust	0.00	0.00	0.00	0.00	51.61	10.80
	On-site vehicle Exhaust	20.37	62.28	5.65	0.06	2.98	2.74
	Employee Vehicles	2.11	0.22	0.22	0.00	0.02	0.01
	<i>Total</i>	<i>22.48</i>	<i>62.50</i>	<i>5.86</i>	<i>0.06</i>	<i>54.61</i>	<i>13.55</i>

Table C-4. Fugitive Dust Summary for Transmission Line, Subtransmission Line, and Telecommunications Construction
(Replaces Table F-4 of PEA Appendix F-1)

Construction Element	Maximum Fugitive Dust Emissions (lb/day)	
	PM10	PM2.5
<i>Road Construction</i>		
Grading	20.23	10.46
<i>Transmission Line Loop-In</i>		
Unpaved Road Dust	119.66	25.38
Paved Road Dust	10.39	1.76
Dig Foundation Dust	7.80	0.39
Total	137.85	27.53
<i>Subtransmission Line</i>		
Unpaved Road Dust	216.50	45.81
Paved Road Dust	11.84	2.00
Dig Foundation Dust	7.80	0.39
Total	236.14	48.20
<i>Telecommunications</i>		
Unpaved Road Dust	48.69	10.31
Paved Road Dust	2.92	0.49
Total	51.61	10.80

Table C-5. Substation Construction - Fugitive Dust Emission
(Replaces Table F-5 of PEA Appendix F-1)

Using Graders	
E =	80 lbs of Total Suspended Particulate Matter/acre-day ^a
PM10 Fraction =	0.489 ^b
Control Efficiency =	60%
^a Emission Factor from AP-42 Section 13.2.3	
^b Source: SCAQMD, <i>Final Methodology to Calculate PM2.5 and PM2.5 Significance Thresholds, Appendix A - Updated CEIDARS Table with PM2.5 Fractions</i> , October 2006.	

Substation	Total Acres Disturbed	Maximum Controlled Fugitive Dust Emissions		Unpaved Road Travel Fugitive Dust ⁴		Total Controlled Fugitive Dust	
		PM10 (lb/day) ^{1,2}	PM2.5 (lb/day) ³	PM10 (lb/day)	PM2.5 (lb/day)	PM10 (lb/day)	PM2.5 (lb/day)
Devers	0.022	0.34	0.07	12.51	2.66	12.85	2.73
Mirage	0.992	15.52	3.23	0.00	0.00	15.52	3.23
Concho	0.000	0.00	0.00	0.00	0.00	0.00	0.00
Indian Wells	0.000	0.00	0.00	0.00	0.00	0.00	0.00
Santa Rosa	0.000	0.00	0.00	0.00	0.00	0.00	0.00
Eisenhower	0.025	0.39	0.08	12.51	2.66	12.90	2.74
Farrell	0.052	0.81	0.17	12.51	2.66	13.32	2.82
Garnet	0.000	0.00	0.00	4.19	0.90	4.19	0.90
Thornhill	0.000	0.00	0.00	4.19	0.90	4.19	0.90
Tamarisk	0.004	0.06	0.01	0.00	0.00	0.06	0.01

¹ The maximum fugitive emissions are assumed to occur during site grading activities.

² Site grading activities for each site were assumed to be completed in one day.

³ PM2.5 fraction of PM10 was assumed to be 0.208 per SCAQMD's *Final Methodology to Calculate PM2.5 and PM2.5 Significance Thresholds, Appendix A - Updated CEIDARS Table with PM2.5 Fractions*.

⁴ Based on adjusted numbers from PEA Appendix F-1: Air Quality Calculations, Table F-9, Unpaved Road Travel During Construction - Fugitive Dust Emissions.

Table C-6. Fugitive Dust from Travel on Unpaved Roads
(adjusts controlled emission rates from Table F-9 of PEA Appendix F-1)

Activity	Uncontrolled Emissions ¹				Controlled Emissions (55%)			
	PM10		PM2.5		PM10		PM2.5	
	(lbs/day)	(lbs/activity)	(lbs/day)	(lbs/activity)	(lbs/day)	(lbs/activity)	(lbs/day)	(lbs/activity)
Subtransmission Line								
<i>Survey</i>								
Worker Traffic	13.90	41.70	2.90	8.80	6.26	18.77	1.31	3.96
1/2-Ton Pick-up	11.60	34.90	2.50	7.40	5.22	15.71	1.13	3.33
					11.48	34.47	2.43	7.29
<i>Roads</i>								
Worker Traffic	18.50	185.40	3.90	39.30	8.33	83.43	1.76	17.69
1-Ton Crew Cab (4X4)	23.30	232.80	4.90	49.40	10.49	104.76	2.21	22.23
Road Grader	27.40	274.20	5.80	58.10	12.33	123.39	2.61	26.15
Track Type Dozer	54.80	548.50	11.60	116.30	24.66	246.83	5.22	52.34
Water Truck	27.40	274.20	5.80	58.10	12.33	123.39	2.61	26.15
					68.13	681.80	14.40	144.54
<i>Pole Framing and Setting</i>								
Worker Traffic	74.20	10904.30	15.70	2311.70	33.39	4906.94	7.07	1040.27
¾-Ton Suburban	23.30	3421.90	4.90	725.50	10.49	1539.86	2.21	326.48
5-Ton Framing Truck 4X4	54.80	4552.40	11.60	965.10	24.66	2048.58	5.22	434.30
30-Ton Line Truck	54.80	4552.40	11.60	965.10	24.66	2048.58	5.22	434.30
Digger Truck	27.40	658.20	5.80	139.50	12.33	296.19	2.61	62.78
Water Truck	27.40	2276.20	5.80	482.60	12.33	1024.29	2.61	217.17
Backhoe	54.80	8062.70	11.60	1709.30	24.66	3628.22	5.22	769.19
Bucket Truck	54.80	8062.70	11.60	1709.30	24.66	3628.22	5.22	769.19
Truck-Mounted Crane	54.80	8062.70	11.60	1709.30	24.66	3628.22	5.22	769.19
30-Ton Crane	27.40	383.90	5.80	81.40	12.33	172.76	2.61	36.63
Cement Truck	27.40	82.30	5.80	17.40	12.33	37.04	2.61	7.83
					216.50	22958.87	45.81	4867.29
<i>Material Delivery</i>								
Worker Traffic	13.90	69.50	2.90	14.70	6.26	31.28	1.31	6.62
60-Foot Flat-Bed Pole Truck	54.80	274.20	11.60	58.10	24.66	123.39	5.22	26.15
Forklift	27.40	137.10	5.80	29.10	12.33	61.70	2.61	13.10
					43.25	216.36	9.14	45.86

Activity	Uncontrolled Emissions ¹				Controlled Emissions (55%)			
	PM10		PM2.5		PM10		PM2.5	
	(lbs/day)	(lbs/activity)	(lbs/day)	(lbs/activity)	(lbs/day)	(lbs/activity)	(lbs/day)	(lbs/activity)
<i>Conductor Installation</i>								
Worker Traffic	74.20	1780.30	15.70	377.40	33.39	801.14	7.07	169.83
Flat-Bed Truck & Trailer (Wire Puller)	27.40	658.20	5.80	139.50	12.33	296.19	2.61	62.78
Flat-Bed Truck & Trailer (Wire Dolly)	27.40	658.20	5.80	139.50	12.33	296.19	2.61	62.78
30-Ton Line Truck	54.80	1316.40	11.60	279.10	24.66	592.38	5.22	125.60
¾-Ton Suburban	23.30	325.90	4.90	69.10	10.49	146.66	2.21	31.10
Water Truck	27.40	658.20	5.80	139.50	12.33	296.19	2.61	62.78
Bucket Truck	54.80	1316.40	11.60	279.10	24.66	592.38	5.22	125.60
Truck-Mounted Crane	54.80	1316.40	11.60	279.10	24.66	592.38	5.22	125.60
					154.85	3613.50	32.76	766.04
<i>Restoration</i>								
Worker Traffic	37.10	1483.60	7.90	314.50	16.70	667.62	3.56	141.53
1-Ton Crew Cab 4X4	23.30	931.10	4.90	197.40	10.49	419.00	2.21	88.83
Water Truck	27.40	1097.00	5.80	232.60	12.33	493.65	2.61	104.67
					39.51	1580.27	8.37	335.03
Max Subtransmission Line					216.50	22958.87	45.81	4867.29
<i>Telecommunications</i>								
Worker Traffic	18.50	2077.00	3.90	440.30	8.33	934.65	1.76	198.14
Crew Truck (gasoline)	23.30	2653.70	4.90	562.60	10.49	1194.17	2.21	253.17
Crew Truck (gasoline)	11.60	989.30	2.50	209.70	5.22	445.19	1.13	94.37
Bucket Truck	54.80	1371.20	11.60	290.70	24.66	617.04	5.22	130.82
Max Telecommunications					48.69	3191.04	10.31	676.49
<i>Transmission Line Loop-In</i>								
<i>Survey</i>								
½-Ton Pick-Up	23.30	69.80	4.90	14.80	10.49	31.41	2.21	6.66
					10.49	31.41	2.21	6.66
<i>Marshalling Yards</i>								
1-Ton Crew Cab	11.60	989.30	2.50	209.70	5.22	445.19	1.13	94.37
Truck, Semi-Tractor	27.40	2331.10	5.80	494.20	12.33	1049.00	2.61	222.39
					17.55	1494.18	3.74	316.76
<i>Roads and Landing Work</i>								
1-Ton Crew Cab	11.60	34.90	2.50	7.40	5.22	15.71	1.13	3.33
Water Truck	82.30	246.80	17.40	52.30	37.04	111.06	7.83	23.54
Lowboy Truck & Trailer	27.40	82.30	5.80	17.40	12.33	37.04	2.61	7.83
					54.59	163.80	11.57	34.70

Activity	Uncontrolled Emissions ¹				Controlled Emissions (55%)			
	PM10		PM2.5		PM10		PM2.5	
	(lbs/day)	(lbs/activity)	(lbs/day)	(lbs/activity)	(lbs/day)	(lbs/activity)	(lbs/day)	(lbs/activity)
<i>Install Foundations</i>								
1-Ton Crew Cab	46.60	791.50	9.90	167.80	20.97	356.18	4.46	75.51
4,000 Gallon Water Truck	54.80	932.40	11.60	197.70	24.66	419.58	5.22	88.97
Concrete Mixer Truck	164.50	2797.30	34.90	593.00	74.03	1258.79	15.71	266.85
					119.66	2034.54	25.38	431.33
<i>Tower Legs, Haul and Erection</i>								
1-Ton Crew Cab	11.60	46.60	2.50	9.90	5.22	20.97	1.13	4.46
30-Ton Crane Truck	27.40	109.70	5.80	23.30	12.33	49.37	2.61	10.49
Truck & Trailer	27.40	109.70	5.80	23.30	12.33	49.37	2.61	10.49
Truck & Trailer	54.80	274.20	11.60	58.10	24.66	123.39	5.22	26.15
					54.54	243.09	11.57	51.57
<i>Tower Assembly</i>								
Crane Truck	54.80	438.80	11.60	93.00	24.66	197.46	5.22	41.85
Pick-Up Truck	34.90	279.30	7.40	59.20	15.71	125.69	3.33	26.64
Crew Cab Flat-Bed	46.60	372.50	9.90	79.00	20.97	167.63	4.46	35.55
Compressor Truck	23.30	186.20	4.90	39.50	10.49	83.79	2.21	17.78
					71.82	574.56	15.21	121.82
<i>Tower and TSP Erection</i>								
Pick-Up Truck	11.60	93.10	2.50	19.70	5.22	41.90	1.13	8.87
Crew Cab Flat-Bed	23.30	186.20	4.90	39.50	10.49	83.79	2.21	17.78
Compressor Truck	11.60	93.10	2.50	19.70	5.22	41.90	1.13	8.87
					20.93	167.58	4.46	35.51
<i>Tower Removal</i>								
Pick-Up Truck	11.60	46.60	2.50	9.90	5.22	20.97	1.13	4.46
Flat-Bed Truck	11.60	46.60	2.50	9.90	5.22	20.97	1.13	4.46
					10.44	41.94	2.25	8.91
<i>Conductor Installation</i>								
Crew Cab Flat-Bed	34.90	349.20	7.40	74.00	15.71	157.14	3.33	33.30
Wire Truck & Trailer	54.80	329.10	11.60	69.80	24.66	148.10	5.22	31.41
Dump Truck (Trash)	27.40	274.20	5.80	58.10	12.33	123.39	2.61	26.15
Pick-Up Truck	11.60	116.40	2.50	24.70	5.22	52.38	1.13	11.12
Log Truck & Trailer	27.40	274.20	5.80	58.10	12.33	123.39	2.61	26.15
Static Truck	27.40	164.50	5.80	34.90	12.33	74.03	2.61	15.71
Lowboy Truck & Trailer	27.40	274.20	5.80	58.10	12.33	123.39	2.61	26.15
					94.91	801.81	20.12	169.97

Activity	Uncontrolled Emissions ¹				Controlled Emissions (55%)			
	PM10		PM2.5		PM10		PM2.5	
	(lbs/day)	(lbs/activity)	(lbs/day)	(lbs/activity)	(lbs/day)	(lbs/activity)	(lbs/day)	(lbs/activity)
<i>Restoration</i>								
Crew Cab	11.60	46.60	2.50	9.90	5.22	20.97	1.13	4.46
Water Truck	82.30	329.10	17.40	69.80	37.04	148.10	7.83	31.41
Lowboy Truck & Trailer	27.40	109.70	5.80	23.30	12.33	49.37	2.61	10.49
					54.59	218.43	11.57	46.35
Max Transmission Line Loop-In					119.66	2034.54	25.38	431.33
Substations								
Devers Substation								
Worker Traffic	27.80	2030.60	5.90	430.50	12.51	913.77	2.66	193.73
Eisenhower Substation								
Worker Traffic	27.80	2030.60	5.90	430.50	12.51	913.77	2.66	193.73
Farrell Substation								
Worker Traffic	27.80	2698.30	5.90	572.00	12.51	1214.24	2.66	257.40
Garnet Substation								
Worker Traffic	9.30	296.70	2.00	62.90	4.19	133.52	0.90	28.31
Thornhill Substation								
Worker Traffic	9.30	741.80	2.00	157.30	4.19	333.81	0.90	70.79
Max Substation					12.51	913.77	2.66	193.73

¹ Rates are from PEA Appendix F-1, Table F-9 Unpaved Road Travel During Construction.

Table C-7. Heavy Duty Vehicle Fugitive Dust Emission Factor For Travel on Paved Roads
(Replaces Emission Factor for Fugitive Dust emissions from Heavy Duty Vehicle Travel on Paved Roads)

Heavy Vehicles on Paved Road Fugitive Dust

Use SCAQMD CEQA Table A9-9-C

$E = V \times F$ (PM10 without street cleaning)

V = vehicles mile traveled

$F = 0.77 * ((G * 0.35)^{0.3})$ lbs/VMT

Assume following reductions per SCAQMD Table XI-C, Mitigation Measure Examples - Fugitive Dust From Paved Roads:

16% control of fugitive dust for street sweeping on local streets

26% control of fugitive dust for street sweeping on arterial/collector streets

	G	F	Control Efficiency	F (controlled)
Local Streets	0.04	0.2140	0.16	0.1797
Collector	0.03	0.1963	0.26	0.1452
Major Streets/Highways	0.012	0.1491	0.26	0.1103
Freeways	0.00065	0.0622	NA	0.0622

Assumed Mix of Roads

0.1	Local streets
0.1	Collector Streets
0.1	Major Streets/Highways
0.7	Freeways

Composite Heavy Vehicle Factor

0.0870 PM10 per VMT

0.169 PM2.5 fraction of PM10 from SCAQMD Table A - Updated CEIDARS Table with PM2.5 Fractions

0.01471 PM2.5 per VMT

Table C-8. Fugitive Dust from Travel on Paved Roads
(adjusts controlled emission rates from Table F-10 of PEA Appendix F-1)

Activity	Number	Days	Hours/Day	VMT/day	F PM10 (lbs/VMT)	F PM2.5 (lbs/VMT)	PM10 (lbs/day)	PM10 lbs activity	PM2.5 (lbs/day)	PM2.5 lbs activity
Subtransmission Line										
<i>Survey</i>										
½-Ton Pick-Up	1	3	10	9.54	0.0116	0.00196	0.1	0.3	0.0	0.1
							0.1	0.3	0.0	0.1
<i>Roads</i>										
1-Ton Crew Cab 4X4	2	10	2	9.54	0.0116	0.00196	0.2	2.2	0.0	0.4
Road Grader	1	10	10	9.54	0.087	0.01471	0.8	8.3	0.1	1.4
Track-Type Dozer	2	10	2.5	9.54	0.087	0.01471	1.7	16.6	0.3	2.8
Water Truck	1	10	10	9.54	0.087	0.01471	0.8	8.3	0.1	1.4
							3.5	35.4	0.6	6.0
<i>Pole Framing and Setting</i>										
¾-Ton Suburban	2	147	10	9.54	0.0116	0.00196	0.2	32.5	0.0	5.5
5-Ton Framing Truck 4X4	2	83	10	9.54	0.087	0.01471	1.7	137.8	0.3	23.3
30-Ton Line Truck	2	83	10	9.54	0.087	0.01471	1.7	137.8	0.3	23.3
Digger Truck	1	24	10	9.54	0.087	0.01471	0.8	19.9	0.1	3.4
Water Truck	1	83	10	9.54	0.087	0.01471	0.8	68.9	0.1	11.6
Backhoe	2	147	10	9.54	0.087	0.01471	1.7	244.0	0.3	41.3
Bucket Truck	2	147	10	9.54	0.087	0.01471	1.7	244.0	0.3	41.3
Truck-Mounted Crane	2	147	10	9.54	0.087	0.01471	1.7	244.0	0.3	41.3
30-Ton Crane	1	14	10	9.54	0.087	0.01471	0.8	11.6	0.1	2.0
Cement Truck	1	3	10	9.54	0.087	0.01471	0.8	2.5	0.1	0.4
							11.8	1143.0	2.0	193.3
<i>Material Delivery</i>										
60-Foot Flat-Bed Pole Truck	2	5	8	9.54	0.087	0.01471	1.7	8.3	0.3	1.4
Forklift	1	5	8	9.54	0.087	0.01471	0.8	4.1	0.1	0.7
							2.5	12.4	0.4	2.1
<i>Conductor Installation</i>										
Flat-Bed Truck & Trailer (Wire Puller)	1	24	6	9.54	0.087	0.01471	0.8	19.9	0.1	3.4
Flat-Bed Truck & Trailer (Wire Dolly)	1	24	6	9.54	0.087	0.01471	0.8	19.9	0.1	3.4
30-Ton Line Truck	2	24	5	9.54	0.087	0.01471	1.7	39.8	0.3	6.7
¾-Ton Suburban	2	14	10	9.54	0.0116	0.00196	0.2	3.1	0.0	0.5
Water Truck	1	24	10	9.54	0.087	0.01471	0.8	19.9	0.1	3.4
Bucket Truck	2	24	6	9.54	0.087	0.01471	1.7	39.8	0.3	6.7
Truck-Mounted Crane	2	24	6	9.54	0.087	0.01471	1.7	39.8	0.3	6.7
							7.7	182.4	1.3	30.8

Activity	Number	Days	Hours/Day	VMT/day	F PM10 (lbs/VMT)	F PM2.5 (lbs/VMT)	PM10 (lbs/day)	PM10 lbs activity	PM2.5 (lbs/day)	PM2.5 lbs activity
<i>Restoration</i>										
1-Ton Crew Cab 4X4	2	40	8	9.54	0.0116	0.00196	0.2	8.9	0.0	1.5
Water Truck	1	40	8	9.54	0.087	0.01471	0.8	33.2	0.1	5.6
							1.1	42.1	0.2	7.1
Max Subtransmission Line							11.84	1143.05	2.00	193.26
<i>Telecommunications</i>										
Crew Truck (gasoline)	2	114	8	14	0.0116	0.00196	0.3	37.0	0.1	6.3
Crew Truck (gasoline)	1	85	8	14	0.0116	0.00196	0.2	13.8	0.0	2.3
Bucket Truck	2	25	8	14	0.087	0.01471	2.4	60.9	0.4	10.3
							2.9	111.7	0.5	18.9
<i>Transmission Line Loop-In</i>										
<i>Survey</i>										
½-Ton Pick-Up	2	3	8	14	0.0116	0.01471	0.3	1.0	0.4	1.2
							0.3	1.0	0.4	1.2
<i>Marshalling Yards</i>										
1-Ton Crew Cab	1	85	2	14	0.0116	0.00196	0.2	13.8	0.0	2.3
Truck, Semi-Tractor	1	85	1	14	0.087	0.01471	1.2	103.5	0.2	17.5
							1.4	117.3	0.2	19.8
<i>Roads and Landing Work</i>										
1-Ton Crew Cab	1	3	5	14	0.0116	0.00196	0.2	0.5	0.0	0.1
Water Truck	3	3	10	14	0.087	0.01471	3.7	11.0	0.6	1.9
Lowboy Truck & Trailer	1	3	4	14	0.087	0.01471	1.2	3.7	0.2	0.6
							5.0	15.1	0.9	2.6
<i>Install Foundations</i>										
1-Ton Crew Cab	4	17	6	14	0.0116	0.00196	0.6	11.0	0.1	1.9
4,000 Gallon Water Truck	2	17	5	14	0.087	0.01471	2.4	41.4	0.4	7.0
Concrete Mixer Truck	6	17	5	14	0.087	0.01471	7.3	124.2	1.2	21.0
							10.4	176.7	1.8	29.9
<i>Tower Legs, Haul and Erection</i>										
1-Ton Crew Cab	1	4	6	14	0.0116	0.00196	0.2	0.6	0.0	0.1
30-Ton Crane Truck	1	4	8	14	0.087	0.01471	1.2	4.9	0.2	0.8
Truck & Trailer	1	4	5	14	0.087	0.01471	1.2	4.9	0.2	0.8
Truck & Trailer	2	5	10	14	0.087	0.01471	2.4	12.2	0.4	2.1
							5.0	22.6	0.9	3.8

Activity	Number	Days	Hours/Day	VMT/day	F PM10 (lbs/VMT)	F PM2.5 (lbs/VMT)	PM10 (lbs/day)	PM10 lbs activity	PM2.5 (lbs/day)	PM2.5 lbs activity
<i>Tower Assembly</i>										
Crane Truck	2	8	8	14	0.087	0.01471	2.4	19.5	0.4	3.3
Pick-Up Truck	3	8	10	14	0.0116	0.00196	0.5	3.9	0.1	0.7
Crew Cab Flat-Bed	4	8	5	14	0.0116	0.00196	0.6	5.2	0.1	0.9
Compressor Truck	2	8	5	14	0.0116	0.00196	0.3	2.6	0.1	0.4
							3.9	31.2	0.7	5.3
<i>Tower and TSP Erection</i>										
Pick-Up Truck	1	8	5	14	0.0116	0.00196	0.2	1.3	0.0	0.2
Crew Cab Flat-Bed	2	8	5	14	0.0116	0.00196	0.3	2.6	0.1	0.4
Compressor Truck	1	8	5	14	0.0116	0.00196	0.2	1.3	0.0	0.2
							0.6	5.2	0.1	0.9
<i>Tower Removal</i>										
Pick-Up Truck	1	4	8	14	0.0116	0.00196	0.2	0.6	0.0	0.1
Flat-Bed Truck	1	4	8	14	0.0116	0.00196	0.2	0.6	0.0	0.1
							0.3	1.3	0.1	0.2
<i>Conductor Installation</i>										
Crew Cab Flat-Bed	3	10	8	14	0.0116	0.00196	0.5	4.9	0.1	0.8
Wire Truck & Trailer	2	6	2	14	0.087	0.01471	2.4	14.6	0.4	2.5
Dump Truck (Trash)	1	10	2	14	0.087	0.01471	1.2	12.2	0.2	2.1
Pick-Up Truck	1	10	10	14	0.0116	0.00196	0.2	1.6	0.0	0.3
Log Truck & Trailer	1	10	2	14	0.087	0.01471	1.2	12.2	0.2	2.1
Static Truck	1	6	2	14	0.087	0.01471	1.2	7.3	0.2	1.2
Lowboy Truck & Trailer	1	10	2	14	0.087	0.01471	1.2	12.2	0.2	2.1
							8.0	65.0	1.3	11.0
<i>Restoration</i>										
Crew Cab	1	4	5	14	0.0116	0.00196	0.2	0.6	0.0	0.1
Water Truck	3	4	10	14	0.087	0.01471	3.7	14.6	0.6	2.5
Lowboy Truck & Trailer	1	4	4	14	0.087	0.01471	1.2	4.9	0.2	0.8
							5.0	20.1	0.9	3.4
Max Transmission Line Loop-In							10.39	176.69	1.76	29.87

Table F-6. Employee Vehicle - Exhaust Emissions

Employee Vehicle Emissions

Emission Factors
from SCAQMD Highest (Most Conservative) EMFAC 2007 Emission
Factors for On-Road Passenger Vehicles and Delivery Trucks

$$E = F * VMT$$

F = Emission factor per passenger vehicle (lb/VMT)

VMT = Vehicle Miles Traveled

VMT per employee = 50 miles (Assumed)

E = Emissions lb/day

Emission Factors for 2008 (lb/VMT)

CO = 0.01055

NOx = 0.00110

ROG = 0.00108

SOx = 0.00001

PM10 = 0.00009

PM2.5 = 0.00005

Emission Summary

Construction Phase	Employee s per day*	CO (lbs/day)	NOx (lbs/day)	ROG (lbs/day)	SOx (lbs/day)	PM10 (lbs/day)	PM2.5 (lbs/day)
Transmission Line Loop- In	12	6.33	0.66	0.65	0.01	0.05	0.03
Subtransmission Lines	47	24.79	2.59	2.54	0.03	0.20	0.12
Devers Substation	6	3.16	0.33	0.32	0.00	0.03	0.02
Mirage Substation	23	12.13	1.27	1.24	0.01	0.10	0.06
Concho Substation	2	1.05	0.11	0.11	0.00	0.01	0.01
Indian Wells Substation	2	1.05	0.11	0.11	0.00	0.01	0.01
Santa Rosa Substation	2	1.05	0.11	0.11	0.00	0.01	0.01
Eisenhower Substation	6	3.16	0.33	0.32	0.00	0.03	0.02
Farrell Substation	6	3.16	0.33	0.32	0.00	0.03	0.02
Garnet Substation	2	1.05	0.11	0.11	0.00	0.01	0.01
Thornhill Substation	2	1.05	0.11	0.11	0.00	0.01	0.01
Tamarisk Substation	4	2.11	0.22	0.22	0.00	0.02	0.01
Telecommunication	4	2.11	0.22	0.22	0.00	0.02	0.01

* This is the maximum number of employees per day expected for this phase of the project

Table F-7. Road Grading - Fugitive Dust Emissions

On-site fugitive dust sources during grading of road

Using Graders	
Emission Factors from AP42 Table 11.9-1	
E=k*0.051*(S^2) for PM10	
E=k*0.040*(S^2.5) for PM2.5	
k=.6 PM10	
k=.031 PM2.5	
S=mean speed	
E=lbs/VMT	
E(PM10)	0.2754 lbs/VMT
E(PM2.5)	0.0193 lbs/VMT
Assume	3 mph grader speed
E(PM10)	0.826 lbs/hr
E(PM2.5)	0.058 lbs/hr
Assume	5 hours per day grading
E(PM10)	4.13 lbs/day/grader
E(PM2.5)	0.29 lbs/day/grader
Assume	1 Grader
E(PM10)	4.1 lbs/day
E(PM2.5)	0.3 lbs/day
Assume	10 days of grading
E(PM10)	41 lbs total activity
E(PM2.5)	3 lbs total activity

Crawler Operation	
Used dozer equation in AP 42 Tables 11.9-1 and 11.9-2	
E(PM10)= k*(s^1.5)/(M^1.4)	
E(PM2.5)= k*5.7*(^1.2)/(M^1.3)	
k= .75 for PM10	
k=0.105 for PM2.5	
s=silt content %	
M= moisture content %	
Assume	
s=	8.5 %
M=	8 %
E(PM10)=	1.011 lb/hr
E(PM2.5)=	0.523 lb/hr
Assume	
10	hrs/day
2	dozers
E(PM10)	20.2 lbs/day
E(PM2.5)	10.5 lbs/day
Assume	
10	days compacting
E(PM10)	202 lbs total activity
E(PM2.5)	105 lbs total activity

Uncontrolled Fugitive Dust Emission Summary

PM10 (lbs/day)	PM10 Total Activity (lbs)	PM2.5 (lbs/day)	PM2.5 Total Activity (lbs)	Activity
4	41	0	3	Using Graders
20	202	10	105	Using Crawlers
24	244	11	107	Total Uncontrolled

Assume 60% control factor for using watering trucks

PM10 (lbs/day)	PM10 Total Activity (lbs)	PM2.5 (lbs/day)	PM2.5 Total Activity (lbs)	Activity
10	97	4	43	Total Controlled

Table F-8. Dig Foundation - Fugitive Dust Emissions

On-site fugitive dust sources during digging foundations

Digger Truck Operation		
Used AP42 11.9-4		
E(TSP)= 1.3 lb/hole		
Assume		
	10	holes per day
	0.6	factor for PM10 (like grader)
	0.03	factor for PM2.5 (like grader)
E(PM10)	7.8	lbs/day
E(PM2.5)	0.4	lbs/day
Assume		
	24	days drilling
E(PM10)	187	lbs total activity
E(PM2.5)	9	lbs total activity

Table F-11. Subtransmission Line Construction - Route Details

Route	Distance (Miles)	
	Paved	Unpaved
Farrell-Garnet (Alternative Route 1) Starting from Devers Substation	6.00	2.33
Farrell-Garnet (Alternative Route 2) Starting from Devers Substation	4.60	4.77
Farrell-Garnet (Alternative Route 3) Starting from Devers Substation	7.00	2.33
Devers Coachella Valley Loop-In Starting from Mirage Substation	0.00	0.95
Mirage-Santa Rosa (Alternative Route 1) Starting from Mirage Substation	0.00	1.42
Mirage-Santa Rosa (Alternative Route 2) Starting from Mirage Substation	2.93	0.00
Bob Hope Dr. & Dinah Shore Dr. Substation Line Reconfiguration (Alternative Route 1) Starting from Mirage Substation	2.67	1.42
Bob Hope & Dinah Shore Dr. Substation Line Reconfiguration (Alternative Route 2) Starting from Mirage Substation	2.77	0.00
Gerald Ford Dr. & Portola Ave. Substation Line Reconfiguration (Alternative Route 1) Starting from Mirage Substation	0.00	2.02
Gerald Ford Dr. & Portola Ave. Substation Line Reconfiguration (Alternative Route 2) Starting from Mirage Substation	2.97	0.57

Notes

1. Based on detailed map of the area. Distances are approximate.

Table F-12. Equipment Exhaust During Transmission Line Construction - Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)
TRANSMISSION LINE LOOP-IN								
Survey								
- 2 ½-Ton Pick-Up	200	3	8	1.4	10.5	11.4	0.0	0.4
- Total Survey				1.4	10.5	11.4	0.0	0.4
Marshalling Yards								
- 1 1-Ton Crew Cab	300	85	2	0.1	0.6	0.1	0.0	0.0
- 1 30-Ton Crane	300	85	2	0.4	1.6	4.0	0.0	0.2
- 2 10,000-Pound Rough-Terrain Forklift	200	85	5	0.7	1.8	8.3	0.0	0.3
- 1 Truck, Semi-Tractor	350	85	1	0.1	0.4	1.3	0.0	0.1
- Total Marshalling Yards				1.3	4.4	13.7	0.0	0.5
Roads and Landing Work								
- 1 1-Ton Crew Cab	300	3	5	0.2	1.6	0.2	0.0	0.0
- 1 Road Grader	350	3	6	1.4	5.3	14.3	0.0	0.5
- 1 Track-Type Dozer	350	3	6	2.3	11.9	21.0	0.0	0.9
- 1 Drum-Type Compactor	250	3	6	1.5	4.2	16.9	0.0	0.6
- 3 Water Truck	350	3	10	3.2	12.3	40.1	0.0	1.9
- 1 Lowboy Truck & Trailer	250	3	4	0.4	1.6	5.3	0.0	0.3
- 1 Excavator	300	3	6	1.3	4.3	13.3	0.0	0.5
- 1 Front-End Loader	350	3	6	1.7	5.8	18.8	0.0	0.7
- Total Roads and Landing Work				12.1	46.9	130.1	0.1	5.4
Install Foundations								
- 4 1-Ton Crew Cab	300	17	6	0.8	7.6	0.8	0.0	0.1
- 2 30-Ton Crane	300	17	5	2.0	7.8	19.9	0.0	0.8
- 1 Front-End Loader	200	17	5	0.8	2.2	9.0	0.0	0.3
- 2 Diggers	500	17	8	4.6	15.3	50.2	0.1	1.8
- 2 4,000-Gallon Water Truck	350	17	5	1.1	4.1	13.4	0.0	0.6
- 6 Concrete Mixer Truck	425	17	5	3.2	12.3	40.1	0.0	1.9
- Total Install Foundations				12.4	49.27	133.36	0.15	5.48
Tower Legs Haul and Erect								
- 1 1-Ton Crew Cab	300	4	6	0.2	1.9	0.2	0.0	0.0
- 1 30-Ton Crane Truck	300	4	8	0.8	3.3	10.7	0.0	0.5
- 1 10,000-Pound Rough-Terrain Forklift	200	4	6	0.4	1.1	5.0	0.0	0.2
- 1 Truck & Trailer	350	4	5	0.5	2.0	6.7	0.0	0.3
- 1 10,000-Pound Rough-Terrain Forklift	200	5	8	0.6	1.5	6.7	0.0	0.2
- 2 Truck & Trailer	350	5	10	2.1	8.2	26.7	0.0	1.3
- Total Tower Legs Haul and Erect				4.7	17.93	55.97	0.06	2.51

Table F-12. Equipment Exhaust During Transmission Line Construction - Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)
Tower Assembly								
- 2 Rough-Terrain Crane	400	8	8	3.2	12.4	31.8	0.0	1.2
- 2 Crane Truck	300	8	8	1.7	6.5	21.4	0.0	1.0
- 2 Rough-Terrain Fork Lift	200	8	5	0.7	1.8	8.3	0.0	0.3
- 3 Pick-Up Truck	300	8	10	2.7	19.8	21.3	0.0	0.8
- 4 Crew Cab Flat-Bed	300	8	5	0.6	6.3	0.7	0.0	0.1
- 2 Compressor Truck	350	8	5	1.1	4.1	13.4	0.0	0.6
- Total Tower Assembly				10.0	50.94	96.90	0.10	3.99
Tower TSP Erection								
- 1 Pick-Up Truck	300	8	5	0.4	3.3	3.6	0.0	0.1
- 2 Crew Cab Flat-Bed	300	8	5	0.3	3.2	0.3	0.0	0.0
- 1 Compressor Truck	350	8	5	0.5	2.0	6.7	0.0	0.3
- 1 Rough-Terrain Crane	500	8	6	1.2	4.7	11.9	0.0	0.5
- Total Tower TSP Erection				2.5	13.2	22.5	0.0	0.9
Tower Removal								
- 1 Pick-Up Truck	300	4	8	0.7	5.3	5.7	0.0	0.2
- 1 Flat-Bed Truck	350	4	8	0.3	2.5	0.3	0.0	0.0
- Total Tower Removal				1.0	7.8	6.0	0.0	0.2
Conductor Installation								
- 3 Crew Cab Flat-Bed Bed	300	10	8	0.8	7.6	0.8	0.0	0.1
- 2 Wire Truck & Trailer	350	6	2	0.4	1.6	5.3	0.0	0.3
- 1 Dump Truck (Trash)	350	10	2	0.2	0.8	2.7	0.0	0.1
- 1 Pick-Up Truck	300	10	10	0.9	6.6	7.1	0.0	0.3
- 2 Manitex	350	10	6	2.3	8.5	27.3	0.0	0.9
- 1 Manitex	350	10	8	1.6	5.7	18.2	0.0	0.6
- 2 Sleeving Rigs	350	10	2	0.6	2.3	8.1	0.0	0.3
- 1 Log Truck & Trailer	500	10	2	0.2	0.8	2.7	0.0	0.1
- 1 Rough-Terrain Fork Lift	350	10	2	0.1	0.4	1.7	0.0	0.1
- 1 580 Case Backhoe	120	6	2	0.2	0.7	1.3	0.0	0.1
- 4 Spacing Cart	10	6	4	0.2	1.0	1.2	0.0	0.1
- 1 Static Truck	350	6	2	0.2	0.8	2.7	0.0	0.1
- 1 Static Tensioner	0	6	2	0.0	0.1	0.1	0.0	0.0
- 2 3-Drum Strawline Puller	300	6	4	1.6	5.7	18.2	0.0	0.6
- 1 60lk Puller	525	6	3	0.6	2.1	6.8	0.0	0.2
- 1 Sag Cat with 2 Winches	350	6	2	0.4	1.4	4.6	0.0	0.2
- 4 D8 Cat	300	6	1	1.2	3.8	12.6	0.0	0.4
- 1 Hughes 500 E Helicopter	650	3	4	1.5	17.6	16.6	1.4	2.3
- 1 Fuel, Helicopter Support Truck	300	3	2	0.2	0.8	2.7	0.0	0.1
- 1 Low Boy Truck & Trailer	500	10	2	0.2	0.8	2.7	0.0	0.1
- Total Conductor Installation				13.4	69.1	143.3	1.5	7.0

Table F-12. Equipment Exhaust During Transmission Line Construction - Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)
Restoration								
- 1 Crew Cab	300	4	5	0.2	1.6	0.2	0.0	0.0
- 1 Road Grader	350	4	6	1.4	5.3	14.3	0.0	0.5
- 1 Track-Type Dozer	350	4	6	2.3	11.9	21.0	0.0	0.9
- 1 Drum-Type Compactor	250	4	6	1.5	4.2	16.9	0.0	0.6
- 3 Water Trucks	350	4	10	3.2	12.3	40.1	0.0	1.9
- 1 Lowboy Truck & Trailer	500	4	4	0.4	1.6	5.3	0.0	0.3
- 1 Front End Loader	350	4	6	1.7	5.8	18.8	0.0	0.7
- 1 Excavator	300	4	6	1.3	4.3	13.3	0.0	0.5
- Total Restoration				12.1	46.9	130.1	0.1	5.4
Maximum Daily Emissions From Transmission Line Construction				13.4	69.1	143.3	1.5	7.0

THIS PAGE IS INTENTIONALLY BLANK

Table F-13. Transmission Line Emission Factors

Off-Road Construction Equipment	Emission Factors						Notes:
	HP (hp)	ROG (lb/hr)	CO (lb/hr)	NOX (lb/hr)	SOX (lb/hr)	PM (lb/hr)	
Bore/Drill Rigs	350	0.1566	0.5631	2.0226	0.0031	0.0640	Used for drillers, and sleeve rigs
Crushers/Process Equipment	250	0.2529	0.7004	2.8190	0.0028	0.0959	Used for compactors
Cranes	300	0.2012	0.7762	1.9878	0.0018	0.0771	Used for cranes
	400	0.2012	0.7762	1.9878	0.0018	0.0771	
	500	0.2012	0.7762	1.9878	0.0018	0.0771	
Excavators	300	0.2175	0.7092	2.2162	0.0023	0.0803	Used for excavators
Forklifts	200	0.0716	0.1822	0.8315	0.0009	0.0254	Used for forklifts
	350	0.0716	0.1822	0.8315	0.0009	0.0254	
Graders	350	0.2360	0.8828	2.3908	0.0023	0.0904	Used for graders
	0	0.0119	0.0617	0.0750	0.0002	0.0046	
	10	0.0119	0.0617	0.0750	0.0002	0.0046	
	300	0.1944	0.7066	2.2771	0.0025	0.0770	
	350	0.1944	0.7066	2.2771	0.0025	0.0770	
Other Construction Equipment	525	0.1944	0.7066	2.2771	0.0025	0.0770	Used for manitex, spacing carts, pullers, and tensioners
Other General Industrial Equipment	650	0.4552	1.5794	4.8663	0.0044	0.1724	
Rubber-Tired Dozers	300	0.3895	1.9869	3.5050	0.0026	0.1495	Used for dozers
	350	0.3895	1.9869	3.5050	0.0026	0.1495	
Tractors/Loaders/Backhoes	120	0.1083	0.3703	0.6510	0.0006	0.0595	Used for all backhoes, excavators, loaders & ditch diggers
	200	0.1598	0.4453	1.7937	0.0019	0.0598	
	300	0.2897	0.9591	3.1387	0.0039	0.1102	
	350	0.2897	0.9591	3.1387	0.0039	0.1102	
	500	0.2897	0.9591	3.1387	0.0039	0.1102	
Source: SCAQMD Air Quality Handbook, Off-Road Emissions Sources - (http://www.aqmd.gov/ceqa/handbook/offroad/offroad.html)							
	HP (hp)	ROG (lb/hr)	CO (lb/hr)	NOX (lb/hr)	SOX (lb/hr)	PM (lb/hr)	
Helicopters	650	0.3677	4.4054	4.1474	0.3483	0.5805	Used for helicopters
Source: EPA 420-R-92-009 - Procedures for Emission Inventory Preparation, Volume IV, Mobile Sources, December 1992							
- (http://www.ntl.bts.gov/docs/AQP.html - Table 5-7, Pg. 185)							
On-Road Vehicles	HP (hp)	ROG (lb/hr)	CO (lb/hr)	NOX (lb/hr)	SOX (lb/hr)	PM (lb/hr)	
Crew & Foreman Trucks (Suburbans) (pounds/mile x 30 miles/hour)	Composite	0.032376	0.316453	0.033086	0.000323	0.002552	Used 'passenger vehicle' emfac
Pick-Up Trucks (pounds/mile) x 30 miles/hour	Composite	0.089781	0.658475	0.711377	0.00077	0.025682	Used 'delivery trucks' emfac
Heavy Duty Trucks and Truck-Mounted Equipment (pounds/mile) x 30 miles/hour	Composite	0.105474	0.40841	1.337405	0.001241	0.064691	Used 'heavy-heavy-duty trucks' emfac
Source: SCAQMD Air Quality Handbook, Emfac2007 (Ver2.3) Emission Factors (On-Road), Scenario Year 2008 - http://www.aqmd.gov/ceqa/handbook/onroad/onroad.html							

THIS PAGE IS INTENTIONALLY BLANK

Table F-14. Equipment Exhaust During Subtransmission Line Construction - Exhaust Emissions									
	Construction	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)
Subtransmission Lines									
Survey									
	1 ½-Ton Pick-Up Truck, 4X4	200	3	10	0.9	6.6	7.1	0.0	0.3
	Total Survey				0.9	6.6	7.1	0.0	0.3
Roads									
	2 1-Ton Crew Cab, 4X4	300	10	2	0.1	1.3	0.1	0.0	0.0
	1 Road Grader	350	10	10	2.4	8.8	23.9	0.0	0.9
	2 Track Type Dozer	350	10	2.5	1.9	9.9	17.5	0.0	0.7
	1 Water Truck	350	10	10	1.1	4.1	13.4	0.0	0.6
	Total Roads				5.5	24.1	54.9	0.0	2.3
Pole Framing and Setting									
	2 ¾-Ton Suburban	300	147	10	0.6	6.3	0.7	0.0	0.1
	2 5-Ton Framing Truck, 4X4	350	83	10	2.1	8.2	26.7	0.0	1.3
	2 30-Ton Line Truck	350	83	10	2.1	8.2	26.7	0.0	1.3
	1 Digger Truck	500	24	10	1.1	4.1	13.4	0.0	0.6
	1 Water Truck	350	83	10	1.1	4.1	13.4	0.0	0.6
	2 Backhoe	350	147	10	5.8	19.2	62.8	0.1	2.2
	2 Bucket Truck	350	147	10	2.1	8.5	27.3	0.0	1.0
	2 Truck Mounted Crane	350	147	10	2.1	8.2	26.7	0.0	1.3
	1 30-Ton Crane	500	14	10	2.0	7.8	19.9	0.0	0.8
	1 Cement Truck	350	3	10	1.1	4.1	13.4	0.0	0.6
	Total Pole Framing and Setting				20.1	78.5	230.9	0.2	9.8
Material Delivery									
	2 60-Foot Flat-Bed Pole Truck	350	5	8	1.7	6.5	21.4	0.0	1.0
	1 Forklift	200	5	8	0.6	1.5	6.7	0.0	0.2
	Total Material Delivery				2.3	8.0	28.1	0.0	1.2
Conductor Installation									
	1 Flat-Bed Truck & Trailer (Wire Puller)	300	24	6	0.6	2.5	8.0	0.0	0.4
	1 Flat-Bed Truck & Trailer (Wire Dolly)	300	24	6	0.6	2.5	8.0	0.0	0.4
	2 30-Ton Line Truck	300	24	5	1.1	4.1	13.4	0.0	0.6
	2 ¾-Ton Suburban	300	14	10	0.6	6.3	0.7	0.0	0.1
	1 Water Truck	350	24	10	1.1	4.1	13.4	0.0	0.6
	2 Bucket Truck	350	24	6	1.3	4.9	16.0	0.0	0.8
	2 Truck Mounted Crane	350	24	6	1.3	4.9	16.0	0.0	0.8
	Total Conductor Installation				6.6	29.2	75.6	0.1	3.7
Restoration									
	2 1-Ton Crew Cab, 4X4	300	40	8	0.5	5.1	0.5	0.0	0.0
	1 Water Truck	350	40	8	0.8	3.3	10.7	0.0	0.5
	Total Restoration				1.4	8.3	11.2	0.0	0.6

Table F-14. Equipment Exhaust During Subtransmission Line Construction - Exhaust Emissions								
Construction	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)
Maximum Daily Emissions From Subtransmission Line Construction				20.1	78.5	230.9	0.2	9.8
Mirage Substation								
Civil								
1 Driller	Composite	50	8	1.0	4.2	10.7	0.0	0.5
2 Crew Truck	Composite	80	2	0.1	1.3	0.1	0.0	0.0
1 14-Ton Crane	Composite	25	4	0.7	2.4	6.4	0.0	0.3
1 Dump Truck	Composite	75	6	0.6	2.5	8.0	0.0	0.4
1 Tractor	Composite	75	6	0.7	2.4	4.6	0.0	0.4
1 5-Ton Truck	Composite	15	4	0.4	1.6	5.3	0.0	0.3
1 Forklift	Composite	75	4	0.3	1.0	2.4	0.0	0.1
1 Ditch Digger	Composite	55	6	1.0	3.5	7.9	0.0	0.4
Total Civil				5.0	18.9	45.7	0.0	2.3
Electrical								
2 Manlift	Composite	100	6	0.9	2.6	4.7	0.0	0.3
1 Pick-Up Truck	Composite	110	2	0.2	1.3	1.4	0.0	0.1
1 14-Ton Crane Truck	Composite	90	6	0.6	2.5	8.0	0.0	0.4
2 Crew Truck	Composite	110	2	0.1	1.3	0.1	0.0	0.0
1 150-Ton Crane	Composite	60	6	1.1	3.6	9.7	0.0	0.4
1 5-Ton Truck	Composite	50	2	0.2	0.8	2.7	0.0	0.1
1 Forklift	Composite	100	6	0.5	1.5	3.6	0.0	0.2
2 Carryall Vehicle	Composite	110	2	0.4	1.6	5.3	0.0	0.3
1 Support Truck	Composite	25	2	0.2	0.8	2.7	0.0	0.1
Total Electrical				4.2	16.0	38.2	0.0	1.9
Transformer Installation								
2 Carryall Vehicle	Composite	22	6	1.3	4.9	16.0	0.0	0.8
1 Manlift	Composite	20	6	0.4	1.3	2.3	0.0	0.2
1 Forklift	Composite	22	6	0.5	1.5	3.6	0.0	0.2
1 50-Ton Crane	Composite	15	6	1.1	3.6	9.7	0.0	0.4
2 Crew Truck	Composite	22	2	0.1	1.3	0.1	0.0	0.0
Total Transformer Installation				3.4	12.5	31.8	0.0	1.6
Maintenance								
1 Foreman Truck	Composite	40	2	0.1	0.6	0.1	0.0	0.0
1 Manlift	Composite	40	6	0.4	1.3	2.3	0.0	0.2
2 Crew Truck	Composite	110	2	0.1	1.3	0.1	0.0	0.0
Total Maintenance				0.6	3.2	2.5	0.0	0.2
Test								
1 Pick-Up Truck	Composite	110	2	0.2	1.3	1.4	0.0	0.1
Total Test				0.2	1.3	1.4	0.0	0.1
Total Mirage Substation				13.43	51.96	119.57	0.12	6.05

Table F-14. Equipment Exhaust During Subtransmission Line Construction - Exhaust Emissions									
	Construction	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)
Concho Substation									
	Electrical								
	1 Carryall Vehicle	Composite	34	2	0.2	0.8	2.7	0.0	0.1
	Test								
	1 Pick-Up Truck	Composite	34	2	0.2	1.3	1.4	0.0	0.1
	Total Concho Substation				0.39	2.13	4.10	0.00	0.18
Indian Wells Substation									
	Electrical								
	1 Carryall Vehicle	Composite	50	2	0.2	0.8	2.7	0.0	0.1
	Test								
	1 Pick-Up Truck	Composite	50	2	0.2	1.3	1.4	0.0	0.1
	Total Indian Wells Substation				0.4	2.1	4.1	0.0	0.2
Santa Rosa Substation									
	Electrical								
	1 Carryall Vehicle	Composite	40	2	0.2	0.8	2.7	0.0	0.1
	Test								
	1 Pick-Up Truck	Composite	40	2	0.2	1.3	1.4	0.0	0.1
	Total Santa Rosa Substation				0.4	2.1	4.1	0.0	0.2
Devers Substation									
	Civil								
	1 Driller	Composite	2	8	1.0	4.2	10.7	0.0	0.5
	1 Crew Truck	Composite	5	2	0.1	0.6	0.1	0.0	0.0
	1 Dump Truck	Composite	5	6	0.6	2.5	8.0	0.0	0.4
	1 Tractor	Composite	5	6	0.7	2.4	4.6	0.0	0.4
	Total Civil				2.5	9.7	23.5	0.0	1.2
	Electrical								
	1 Manlift	Composite	45	6	0.4	1.3	2.3	0.0	0.2
	1 Pick-Up Truck	Composite	60	2	0.2	1.3	1.4	0.0	0.1
	1 Crew Truck	Composite	60	2	0.1	0.6	0.1	0.0	0.0
	1 150-Ton Crane	Composite	10	6	1.1	3.6	9.7	0.0	0.4
	1 Forklift	Composite	40	6	0.5	1.5	3.6	0.0	0.2
	1 Carryall Vehicle	Composite	60	2	0.2	0.8	2.7	0.0	0.1
	Total Electrical				2.4	9.1	19.7	0.0	1.0

Table F-14. Equipment Exhaust During Subtransmission Line Construction - Exhaust Emissions									
	Construction	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)
	Maintenance								
	1 Foreman Truck	Composite	5	2	0.1	0.6	0.1	0.0	0.0
	1 Crew Truck	Composite	10	2	0.1	0.6	0.1	0.0	0.0
	Total Maintenance				0.1	1.3	0.1	0.0	0.0
	Test								
	1 Pick-Up Truck	Composite	20	2	0.2	1.3	1.4	0.0	0.1
	Total Test				0.2	1.3	1.4	0.0	0.1
	Total Devers Substation				5.2	21.5	44.8	0.0	2.3
	Eisenhower Substation								
	Civil								
	1 Driller	Composite	5	8	1.0	4.2	10.7	0.0	0.5
	1 Crew Truck	Composite	15	2	0.1	0.6	0.1	0.0	0.0
	1 Dump Truck	Composite	15	6	0.6	2.5	8.0	0.0	0.4
	1 Tractor	Composite	15	6	0.7	2.4	4.6	0.0	0.4
	1 Ditch Digger	Composite	5	6	1.0	3.5	7.9	0.0	0.4
	Total Civil				3.5	13.2	31.4	0.0	1.7
	Electrical								
	1 Manlift	Composite	35	6	0.4	1.3	2.3	0.0	0.2
	1 Crew Truck	Composite	45	2	0.1	0.6	0.1	0.0	0.0
	1 150-Ton Crane	Composite	20	6	1.1	3.6	9.7	0.0	0.4
	1 Forklift	Composite	45	6	0.5	1.5	3.6	0.0	0.2
	1 Carryall Vehicle	Composite	45	2	0.2	0.8	2.7	0.0	0.1
	Total Electrical				2.3	7.8	18.3	0.0	0.9
	Maintenance								
	1 Foreman Truck	Composite	5	2	0.1	0.6	0.1	0.0	0.0
	1 Crew Truck	Composite	10	2	0.1	0.6	0.1	0.0	0.0
	Total Maintenance				0.1	1.3	0.1	0.0	0.0
	Test								
	1 Pick-Up Truck	Composite	45	2	0.2	1.3	1.4	0.0	0.1
	Total Test				0.2	1.3	1.4	0.0	0.1
	Total Eisenhower Substation				6.1	23.7	51.3	0.1	2.6

Table F-14. Equipment Exhaust During Subtransmission Line Construction - Exhaust Emissions									
	Construction	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)
Farrell Substation									
Civil									
	1 Driller	Composite	10	8	1.0	4.2	10.7	0.0	0.5
	1 Crew Truck	Composite	20	2	0.1	0.6	0.1	0.0	0.0
	1 Dump Truck	Composite	20	6	0.6	2.5	8.0	0.0	0.4
	1 Tractor	Composite	20	6	0.7	2.4	4.6	0.0	0.4
	1 Ditch Digger	Composite	10	6	1.0	3.5	7.9	0.0	0.4
	Total Civil				3.5	13.2	31.4	0.0	1.7
Electrical									
	1 Manlift	Composite	40	6	0.4	1.3	2.3	0.0	0.2
	1 Crew Truck	Composite	55	2	0.1	0.6	0.1	0.0	0.0
	1 150-Ton Crane	Composite	25	6	1.1	3.6	9.7	0.0	0.4
	1 Forklift	Composite	55	6	0.5	1.5	3.6	0.0	0.2
	1 Carryall Vehicle	Composite	55	2	0.2	0.8	2.7	0.0	0.1
	Total Electrical				2.3	7.8	18.3	0.0	0.9
Maintenance									
	1 Foreman Truck	Composite	5	2	0.1	0.6	0.1	0.0	0.0
	1 Crew Truck	Composite	10	2	0.1	0.6	0.1	0.0	0.0
	Total Maintenance				0.1	1.3	0.1	0.0	0.0
Test									
	1 Pick-Up Truck	Composite	55	2	0.2	1.3	1.4	0.0	0.1
	Total Test				0.2	1.3	1.4	0.0	0.1
	Total Farrell Substation				6.1	23.7	51.3	0.1	2.6
Garnet Substation									
Electrical									
	1 Carryall Vehicle	Composite	16	2	0.2	0.8	2.7	0.0	0.1
Test									
	1 Pick-Up Truck	Composite	16	2	0.2	1.3	1.4	0.0	0.1
	Total Garnet Substation				0.4	2.1	4.1	0.0	0.2
Thornhill Substation									
Electrical									
	1 Carryall Vehicle	Composite	40	2	0.2	0.8	2.7	0.0	0.1
Test									
	1 Pick-Up Truck	Composite	40	2	0.2	1.3	1.4	0.0	0.1
	Total Thornhill Substation				0.4	2.1	4.1	0.0	0.2

Table F-14. Equipment Exhaust During Subtransmission Line Construction - Exhaust Emissions									
	Construction	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)
Tamarisk Substation									
Civil									
	1 Crew Truck	Composite	5	2	0.1	0.6	0.1	0.0	0.0
	1 Dump Truck	Composite	5	6	0.6	2.5	8.0	0.0	0.4
	1 Tractor	Composite	5	6	0.7	2.4	4.6	0.0	0.4
	Total Civil				1.4	5.5	12.7	0.0	0.8
Electrical									
	1 Manlift	Composite	5	6	0.4	1.3	2.3	0.0	0.2
	1 Pick-Up Truck	Composite	40	2	0.2	1.3	1.4	0.0	0.1
	1 Crew Truck	Composite	40	2	0.1	0.6	0.1	0.0	0.0
	1 150-Ton Crane	Composite	2	6	1.1	3.6	9.7	0.0	0.4
	1 Forklift	Composite	5	6	0.5	1.5	3.6	0.0	0.2
	1 Carryall Vehicle	Composite	40	2	0.2	0.8	2.7	0.0	0.1
	Total Electrical				2.4	9.1	19.7	0.0	1.0
Maintenance									
	1 Foreman Truck	Composite	1	2	0.1	0.6	0.1	0.0	0.0
	2 Crew Truck	Composite	2	2	0.1	1.3	0.1	0.0	0.0
	Total Maintenance				0.2	1.9	0.2	0.0	0.0
Test									
	1 Pick-Up Truck	Composite	30	2	0.2	1.3	1.4	0.0	0.1
	Total Test				0.2	1.3	1.4	0.0	0.1
	Total Tamarisk Substation				4.2	17.9	34.1	0.0	1.8
Note: Each simultaneous construction phase is calculated separately. Maximum daily emissions are for each construction segment are the maximum daily simultaneous emissions and are bold, italicized, and underlined.									

Table F-15. Subtransmission Line Emission Factors

Off-Road Construction Equipment		Emission Factors					Notes:	
	HP (hp)	ROG (lb/hr)	CO (lb/hr)	NOX (lb/hr)	SOX (lb/hr)	PM (lb/hr)		
Aerial Lifts	Composite	0.0746	0.2200	0.3885	0.0004	0.0269	Used for manlifts	
Bore/Drill Rigs	Composite	0.1295	0.5281	1.3416	0.0017	0.0591	Used for drillers, and sleeve rigs	
	500	0.2012	0.7762	1.9878	0.0018	0.0771		
Cranes	Composite	0.1778	0.6011	1.6100	0.0014	0.0715	Used for all cranes	
Excavators	Composite	0.1695	0.5828	1.3249	0.0013	0.0727	Used for excavators and ditch diggers	
	200	0.0716	0.1822	0.8315	0.0009	0.0254		
Forklifts	Composite	0.0799	0.2422	0.5982	0.0006	0.0324	Used for forklifts	
Graders	350	0.2360	0.8828	2.3908	0.0023	0.0904	Used for graders	
Off-Highway Trucks	Composite	0.2730	0.8499	2.7256	0.0027	0.0989	Used for all diesel trucks & carryall vehicles	
Other Material Handling Equipment	Composite	0.1952	0.6041	1.7655	0.0015	0.0786	Used for cable puller & conductor tensioner	
Other Construction Equipment	Composite	0.1215	0.4504	1.1575	0.0013	0.0503	Used for cable dollies	
Rubber-Tired Dozers	350	0.3895	1.9869	3.5050	0.0026	0.1495	Used for dozers	
	350	0.2897	0.9591	3.1387	0.0039	0.1102		
Tractors/Loaders/Backhoes	Composite	0.1204	0.4063	0.7746	0.0008	0.0599	Used for all backhoes & ditch diggers	
Source: SCAQMD Air Quality Handbook, Off-Road Emissions Sources - (http://www.aqmd.gov/ceqa/handbook/offroad/offroad.html)								
On-Road Vehicles		HP (hp)	ROG (lb/hr)	CO (lb/hr)	NOX (lb/hr)	SOX (lb/hr)	PM (lb/hr)	
Crew & Foreman Trucks (Suburbans) (pounds/mile x 30 miles/hour)	Composite	0.032376	0.316453	0.033086	0.000323	0.002552	Used 'passenger vehicle' emfac	
Pickup Trucks (pounds/mile) x 30 miles/hour	Composite	0.089781	0.658475	0.711377	0.00077	0.025682	Used 'delivery trucks' emfac	
Heavy Duty Trucks and Truck-Mounted Equipment (pounds/mile) x 30 miles/hour	Composite	0.105474	0.40841	1.337405	0.001241	0.064691	Used 'heavy-heavy-duty trucks' emfac	
Source: SCAQMD Air Quality Handbook, Emfac2007 (Ver2.3) Emission Factors (On-Road), Scenario Year 2008 - http://www.aqmd.gov/ceqa/handbook/onroad/onroad.html								

THIS PAGE IS INTENTIONALLY BLANK

Table F-16. Equipment Exhaust During Telecommunication Construction - Exhaust Emissions

Construction Phase	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)	
Mirage-Santa Rosa									
Cable Construction									
2	Bucket Truck	Composite	5	8	1.7	6.5	21.4	0.0	1.0
1	Pick-Up	Composite	5	8	0.0	0.2	0.2	0.0	0.0
1	2-Axle Trailer	Composite	5	8	1.6	4.8	14.1	0.0	0.6
Total Cable Construction					3.3	11.5	35.7	0.0	1.7
Receive and Loadout									
1	5-Ton Forklift	Composite	1	8	0.6	1.9	4.8	0.0	0.3
1	Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Receive and Loadout					0.7	2.1	5.0	0.0	0.3
Clean-Up									
2	Bucket Truck	Composite	1	8	1.7	6.5	21.4	0.0	1.0
1	Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up					1.7	6.7	21.6	0.0	1.0
Total Mirage Santa Rosa					5.65	20.37	62.28	0.06	2.98
Farrell-Garnet									
Cable Construction									
2	Bucket Truck	Composite	18	8	1.7	6.5	21.4	0.0	1.0
1	Pick-Up	Composite	18	8	0.0	0.2	0.2	0.0	0.0
1	2-Axle Trailer	Composite	18	8	1.6	4.8	14.1	0.0	0.6
Total Cable Construction					3.3	11.5	35.7	0.0	1.7
Receive and Loadout									
1	5-Ton Forklift	Composite	1	8	0.6	1.9	4.8	0.0	0.3
1	Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Receive and Loadout					0.7	2.1	5.0	0.0	0.3
Clean-Up									
2	Bucket Truck	Composite	1	8	1.7	6.5	21.4	0.0	1.0
1	Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up					1.7	6.7	21.6	0.0	1.0
Total Farrel Garnet					5.65	20.37	62.28	0.06	2.98
Devers									
Equipment Installation									
2	Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Cable Construction					0.0	0.4	0.4	0.0	0.0
Circuit Installation									
2	Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Circuit Installation					0.0	0.4	0.4	0.0	0.0

Table F-16. Equipment Exhaust During Telecommunication Construction - Exhaust Emissions

Construction Phase	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)
Clean-Up								
1 Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up				0.0	0.2	0.2	0.0	0.0
Total Devers				0.12	0.88	0.95	0.00	0.03
Mirage								
Equipment Installation								
2 Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Cable Construction				0.0	0.4	0.4	0.0	0.0
Circuit Installation								
2 Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Circuit Installation				0.0	0.4	0.4	0.0	0.0
Clean-Up								
1 Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up				0.0	0.2	0.2	0.0	0.0
Total Mirage				0.12	0.88	0.95	0.00	0.03
Tamarisk								
Equipment Installation								
2 Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Cable Construction				0.0	0.4	0.4	0.0	0.0
Circuit Installation								
2 Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Circuit Installation				0.0	0.4	0.4	0.0	0.0
Clean-Up								
1 Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up				0.0	0.2	0.2	0.0	0.0
Total Tamarisk				0.12	0.88	0.95	0.00	0.03
Eisenhower								
Equipment Installation								
2 Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Cable Construction				0.0	0.4	0.4	0.0	0.0
Circuit Installation								
2 Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Circuit Installation				0.0	0.4	0.4	0.0	0.0
Clean-Up								
1 Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up				0.0	0.2	0.2	0.0	0.0
Total Eisenhower				0.12	0.88	0.95	0.00	0.03

Table F-16. Equipment Exhaust During Telecommunication Construction - Exhaust Emissions

Construction Phase	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)
Concho								
Equipment Installation								
2 Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Cable Construction				0.0	0.4	0.4	0.0	0.0
Circuit Installation								
2 Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Circuit Installation				0.0	0.4	0.4	0.0	0.0
Clean-Up								
1 Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up				0.0	0.2	0.2	0.0	0.0
Total Concho				0.12	0.88	0.95	0.00	0.03
Indian Wells								
Equipment Installation								
2 Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Cable Construction				0.0	0.4	0.4	0.0	0.0
Circuit Installation								
2 Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Circuit Installation				0.0	0.4	0.4	0.0	0.0
Clean-Up								
1 Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up				0.0	0.2	0.2	0.0	0.0
Total Indian Wells				0.12	0.88	0.95	0.00	0.03
Santa Rosa								
Equipment Installation								
2 Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Cable Construction				0.0	0.4	0.4	0.0	0.0
Circuit Installation								
2 Pick-Up	Composite	6	8	0.0	0.4	0.4	0.0	0.0
Total Circuit Installation				0.0	0.4	0.4	0.0	0.0
Clean-Up								
1 Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up				0.0	0.2	0.2	0.0	0.0
Total Santa Rosa				0.12	0.88	0.95	0.00	0.03

Table F-16. Equipment Exhaust During Telecommunication Construction - Exhaust Emissions

Construction Phase	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)
Thornhill								
Equipment Installation								
1 Pick-Up	Composite	6	8	0.0	0.2	0.2	0.0	0.0
Total Cable Construction				0.0	0.2	0.2	0.0	0.0
Circuit Installation								
1 Pick-Up	Composite	6	8	0.0	0.2	0.2	0.0	0.0
Total Circuit Installation				0.0	0.2	0.2	0.0	0.0
Clean-Up								
1 Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up				0.0	0.2	0.2	0.0	0.0
Total Thornhill				0.07	0.53	0.57	0.00	0.02
Garnet								
Equipment Installation								
1 Pick-up	Composite	6	8	0.0	0.2	0.2	0.0	0.0
Total Cable Construction				0.0	0.2	0.2	0.0	0.0
Circuit Installation								
1 Pick-Up	Composite	6	8	0.0	0.2	0.2	0.0	0.0
Total Circuit Installation				0.0	0.2	0.2	0.0	0.0
Clean-Up								
1 Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up				0.0	0.2	0.2	0.0	0.0
Total Garnet				0.07	0.53	0.57	0.00	0.02
Farrell								
Equipment Installation								
1 Pick-Up	Composite	6	8	0.0	0.2	0.2	0.0	0.0
Total Cable Construction				0.0	0.2	0.2	0.0	0.0
Circuit Installation								
1 Pick-Up	Composite	6	8	0.0	0.2	0.2	0.0	0.0
Total Circuit Installation				0.0	0.2	0.2	0.0	0.0
Clean-Up								
1 Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up				0.0	0.2	0.2	0.0	0.0
Total Farrell				0.07	0.53	0.57	0.00	0.02

Table F-16. Equipment Exhaust During Telecommunication Construction - Exhaust Emissions

Construction Phase	HP	Duration (days)	Usage (hour/day)	ROG Emissions (lb/day)	CO Emissions (lb/day)	NOX Emissions (lb/day)	SOX Emissions (lb/day)	PM10 Emissions (lb/day)
EDOM Hill								
Equipment Installation								
1 Pick-Up	Composite	6	8	0.0	0.2	0.2	0.0	0.0
Total Cable Construction				0.0	0.2	0.2	0.0	0.0
Circuit Installation								
1 Pick-Up	Composite	6	8	0.0	0.2	0.2	0.0	0.0
Total Circuit Installation				0.0	0.2	0.2	0.0	0.0
Clean-Up								
1 Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up				0.0	0.2	0.2	0.0	0.0
Total EDOM Hills				0.07	0.53	0.57	0.00	0.02
Palm Springs								
Equipment Installation								
1 Pick-Up	Composite	6	8	0.0	0.2	0.2	0.0	0.0
Total Cable Construction				0.0	0.2	0.2	0.0	0.0
Circuit Installation								
1 Pick-Up	Composite	6	8	0.0	0.2	0.2	0.0	0.0
Total Circuit Installation				0.0	0.2	0.2	0.0	0.0
Clean-Up								
1 Pick-Up	Composite	1	8	0.0	0.2	0.2	0.0	0.0
Total Clean-Up				0.0	0.2	0.2	0.0	0.0
Total Palm Springs				0.07	0.53	0.57	0.00	0.02
MAX DAILY EMISSIONS DURING CONSTRUCTION				5.6	20.4	62.3	0.1	3.0

Note: Each simultaneous construction phase is calculated separately. Maximum daily emissions are for each construction segment are the maximum daily simultaneous emissions and are bold, italicized, and underlined. Annual emissions are the sum of all construction phases.

THIS PAGE IS INTENTIONALLY BLANK

Table F-17. Telecommunication Equipment Emission Factors

Off-Road Construction Equipment	Emission Factors						Notes:
	HP (hp)	ROG (lb/hr)	CO (lb/hr)	NOX (lb/hr)	SOX (lb/hr)	PM (lb/hr)	
Forklifts	Composite	0.0799	0.2422	0.5982	0.0006	0.0324	Used for forklifts
Off-Highway Trucks	Composite	0.2730	0.8499	2.7256	0.0027	0.0989	Used for all diesel trucks & carryall vehicles
Other Material Handling Equipment	Composite	0.1952	0.6041	1.7655	0.0015	0.0786	Used for cable puller & conductor tensioner
Source: SCAQMD Air Quality Handbook, Off-Road Emissions Sources - (http://www.aqmd.gov/ceqa/handbook/offroad/offroad.html)							
On-Road Vehicles	HP (hp)	ROG (lb/hr)	CO (lb/hr)	NOX (lb/hr)	SOX (lb/hr)	PM (lb/hr)	Notes:
	HP (hp)	ROG (lb/hr)	CO (lb/hr)	NOX (lb/hr)	SOX (lb/hr)	PM (lb/hr)	
Crew & Foreman Trucks (Suburbans) (pounds/mile x 30 miles/hour)	Composite	0.001079	0.010548	0.001103	1.08E-05	0.000085	Used 'passenger vehicle' emfac
Pickup Trucks (pounds/mile) x 30 miles/hour	Composite	0.002993	0.021949	0.023713	2.57E-05	0.000856	Used 'delivery trucks' emfac
Heavy Duty Trucks and Truck-Mounted Equipment (pounds/miles) x 30 miles/hour	Composite	0.105474	0.40841	1.337405	0.001241	0.064691	Used 'heavy-heavy-duty trucks' emfac
Source: SCAQMD Air Quality Handbook, Emfac2007 (Ver2.3) Emission Factors (On-Road), Scenario Year 2008 - http://www.aqmd.gov/ceqa/handbook/onroad/onroad.html							

THIS PAGE IS INTENTIONALLY BLANK

Table F-18. Maximum Project CO2 Emissions Summary

Construction Phase	Maximum Emissions (tons/project)	
	CO2	
<i>Transmission Line Loop-In¹</i>		
On-Site Vehicle Exhaust		356.27
Employee Vehicles		19.31
Total		375.58
<i>Subtransmission Line²</i>		
On-Site Vehicle Exhaust		1377.29
Employee Vehicles		141.32
Total		1518.62
<i>Devers Substation Construction</i>		
On-Site Vehicle Exhaust		36.03
Employee Vehicles		12.05
Total		48.09
<i>Mirage Substation Construction</i>		
On-Site Vehicle Exhaust		319.04
Employee Vehicles		128.29
Total		447.33
<i>Concho Substation Construction</i>		
On-Site Vehicle Exhaust		7.07
Employee Vehicles		3.72
Total		10.79
<i>Indian Wells Substation Construction</i>		
On-Site Vehicle Exhaust		10.40
Employee Vehicles		5.48
Total		15.87
<i>Santa Rosa Substation Construction</i>		
On-Site Vehicle Exhaust		8.32
Employee Vehicles		4.38
Total		12.70
<i>Eisenhower Substation Construction</i>		
On-Site Vehicle Exhaust		44.32
Employee Vehicles		12.05
Total		56.37
<i>Farrell Substation Construction</i>		
On-Site Vehicle Exhaust		58.97
Employee Vehicles		15.89
Total		74.85

Table F-18. Maximum Project CO2 Emissions Summary

Construction Phase	Maximum Emissions (tons/project)
	CO2
<i>Garnet Substation Construction</i>	
On-Site Vehicle Exhaust	3.33
Employee Vehicles	1.75
Total	5.08
<i>Thornhill Substation Construction</i>	
On-Site Vehicle Exhaust	8.32
Employee Vehicles	4.38
Total	12.70
<i>Tamarisk Substation Construction</i>	
On-Site Vehicle Exhaust	17.42
Employee Vehicles	14.05
Total	31.47
<i>Telecommunications Line</i>	
On-Site Vehicle Exhaust	125.82
Employee Vehicles	14.05
Total	139.87
Project Total Emissions	2749.31

Table F-19. Employee Vehicle - CO2 Exhaust Emissions

Employee Vehicle Emissions

Emission Factors from SCAQMD Highest (Most Conservative) EMFAC 2007 Emission Factors for On-Road Passenger Vehicles and Delivery Trucks	
E=F* VMT*DAYS/2000	
F = Emission factor per passenger vehicle (lb/VMT)	
VMT = Vehicle Miles Traveled	
VMT per employee =	50 miles (assumed)
DAYS = Employee-days traveling to/from project	
E = Emissions tons/project	
Emission Factors for 2008 (lb/VMT)	
CO2 =	1.09553

Emission Summary

Construction Phase	Employee-days per project*	CO2 (tons/project)
Transmission Line Loop-In	705	19.31
Subtransmission Lines	5160	141.32
Devers Substation	440	12.05
Mirage Substation	4684	128.29
Concho Substation	136	3.72
Indian Wells Substation	200	5.48
Santa Rosa Substation	160	4.38
Eisenhower Substation	440	12.05
Farrell Substation	580	15.89
Garnet Substation	64	1.75
Thornhill Substation	160	4.38
Tamarisk Substation	195	5.34
Telecommunication	513	14.05
Total Emissions		368.02

* Computed by calculating the person-days for each activity with the construction phase and summing over all activities.

Table F-20. Subtransmission Line Construction - Route Details		
Route	Distance (Miles)	
	Paved	Unpaved
Farrell-Garnet (Alternative Route 1) Starting from Devers Substation	6.00	2.33
Farrell-Garnet (Alternative Route 2) Starting from Devers Substation	4.60	4.77
Farrell-Garnet (Alternative Route 3) Starting from Devers Substation	7.00	2.33
Devers Coachella Loo Starting from Mirage Substation	0.00	0.95
Mirage-Santa Rosa (Alternative Route 1) Starting from Mirage Substation	0.00	1.42
Mirage-Santa Rosa (Alternative Route 2) Starting from Mirage Substation	2.93	0.00
Bob Hope Dr. & Dinah Shore Dr. Substation Line Reconfiguration (Alternative Route 1) Starting from Mirage Substation	2.67	1.42
Bob Hope Dr. & Dinah Shore Dr. Substation Line Reconfiguration (Alternative Route 2) Starting from Mirage Substation	2.77	0.00
Gerald Ford Dr. & Portola Ave. Substation Line Reconfiguration (Alternative Route 1) Starting from Mirage Substation	0.00	2.02
Gerald Ford Dr. & Portola Ave. Substation Line Reconfiguration (Alternative Route 2) Starting from Mirage Substation	2.97	0.57
Notes		
1. Based on detailed map of the area. Distances are approximate.		

Table F-21. Equipment Exhaust During Transmission Line Construction - CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (pounds/day)	CO2 Emissions (tons/project)
TRANSMISSION LINE LOOP-IN					
<u>Survey</u>					
- 2 ½-Ton Pick-Up	200	3	8	1305.3	2.0
- Total Survey				1305.3	2.0
<u>Marshalling Yards</u>					
- 1 1-Ton Crew Cab	300	85	2	66.0	2.8
- 1 30-Ton Crane	300	85	2	360.2	15.3
- 10,000-Pound Rough-Terrain					
- 2 Forklift	200	85	5	771.0	32.8
- 1 Truck, Semi-Tractor	350	85	1	126.3	5.4
- Total Marshalling Yards				1323.5	56.2
<u>Roads and Landing Work</u>					
- 1 1-Ton Crew Cab	300	3	5	164.9	0.2
- 1 Road Grader	350	3	6	1377.0	2.1
- 1 Track-Type Dozer	350	3	6	1589.4	2.4
- 1 Drum-Type Compactor	250	3	6	1467.0	2.2
- 3 Water Truck	350	3	10	3789.6	5.7
- 1 Lowboy Truck & Trailer	250	3	4	505.3	0.8
- 1 Excavator	300	3	6	1402.2	2.1
- 1 Front End Loader	350	3	6	2069.4	3.1
- Total Roads and Landing Work				12364.8	18.5
<u>Install Foundations</u>					
- 4 1-Ton Crew Cab	300	17	6	791.7	6.7
- 2 30-Ton Crane	300	17	5	1801.0	15.3
- 1 Front End Loader	200	17	5	858.5	7.3
- 2 Digger	500	17	8	5518.4	46.9

Table F-21. Equipment Exhaust During Transmission Line Construction - CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (pounds/day)	CO2 Emissions (tons/project)
- 2 4,000 Gallon Water Truck	350	17	5	1263.2	10.7
- 6 Concrete Mixer Truck	425	17	5	3789.6	32.2
- Total Install Foundations				14022.37	119.19
<u>Tower Legs Haul and Erect</u>					
- 1 Ton Crew Cab	300	4	6	197.9	0.4
- 1 30-Ton Crane Truck	300	4	8	1010.6	2.0
- 10,000-Pound Rough-Terrain					
- 1 Forklift	200	4	6	462.6	0.9
- 1 Truck & Trailer	350	4	5	631.6	1.3
- 10,000-Pound Rough-Terrain					
- 1 Forklift	200	5	8	616.8	1.5
- 2 Truck & Trailer	350	5	10	2526.4	6.3
- Total Tower Legs Haul and Erect				5445.88	12.46
<u>Tower Assembly</u>					
- 2 Rough-Terrain Crane	400	8	8	2881.6	11.5
- 2 Crane Truck	300	8	8	2021.1	8.1
- 2 Rough-Terrain Fork Lift	200	8	5	771.0	3.1
- 3 Pick-Up Truck	300	8	10	2447.5	9.8
- 4 Crew Cab Flat-Bed	300	8	5	659.7	2.6
- 2 Compressor Truck	350	8	5	1263.2	5.1
- Total Tower Assembly				10044.13	40.18

Table F-21. Equipment Exhaust During Transmission Line Construction - CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (pounds/day)	CO2 Emissions (tons/project)
<u>Tower TSP Erection</u>					
- 1 Pick-Up Truck	300	8	5	407.9	1.6
- 2 Crew Cab Flat-Bed	300	8	5	329.9	1.3
- 1 Compressor Truck	350	8	5	631.6	2.5
- 1 Rough-Terrain Crane	500	8	6	1080.6	4.3
- Total Tower TSP Erection				2450.0	9.8
<u>Tower Removal</u>					
- 1 Pick-Up Truck	300	4	8	652.7	1.3
- 1 Flat-Bed Truck	350	4	8	263.9	0.5
- Total Tower Removal				916.6	1.8
<u>Conductor Installation</u>					
- 3 Crew Cab Flat-Bed Bed	300	10	8	791.7	4.0
- 2 Wire Truck & Trailer	350	6	2	505.3	1.5
- 1 Dump Truck (Trash)	350	10	2	252.6	1.3
- 1 Pick-Up Truck	300	10	10	815.8	4.1
- 2 Manitex	350	10	6	3050.4	15.3
- 1 Manitex	350	10	8	2033.6	10.2
- 2 Sleeving Rigs	350	10	2	1245.2	6.2
- 1 Log Truck & Trailer	500	10	2	252.6	1.3
- 1 Rough-Terrain Fork Lift	350	10	2	154.2	0.8
- 1 580 Case Backhoe	120	6	2	103.4	0.3
- 4 Spacing Cart	10	6	4	161.6	0.5
- 1 Static Truck	350	6	2	252.6	0.8
- 1 Static Tensioner	0	6	2	20.2	0.1
- 2 3-Drum Strawline Puller	300	6	4	2033.6	6.1
- 1 60lk Puller	525	6	3	762.6	2.3
- 1 Sag Cat with 2 Winches	350	6	2	508.4	1.5

Table F-21. Equipment Exhaust During Transmission Line Construction - CO2 Exhaust Emissions

	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (pounds/day)	CO2 Emissions (tons/project)
Construction					
- 4 D8 Cat	300	6	1	1379.6	4.1
- 1 Hughes 500 E Helicopter	650	3	4	6343.8	9.5
- 1 Fuel, Helicopter Support Truck	300	3	2	252.6	0.4
- 1 Lowboy Truck & Trailer	500	10	2	252.6	1.3
- Total Conductor Installation				21172.6	71.3
Restoration					
- 1 Crew Cab	300	4	5	164.9	0.3
- 1 Road Grader	350	4	6	1377.0	2.8
- 1 Track-Type Dozer	350	4	6	1589.4	3.2
- 1 Drum-Type Compactor	250	4	6	1467.0	2.9
- 3 Water Truck	350	4	10	3789.6	7.6
- 1 Lowboy Truck & Trailer	500	4	4	505.3	1.0
- 1 Front End Loader	350	4	6	2069.4	4.1
- 1 Excavator	300	4	6	1402.2	2.8
- Total Restoration				12364.8	24.7
Maximum Daily Emissions from Transmission Line Construction					356.3

Table F-22. Transmission Line Emission Factors

<u>Off-Road Construction Equipment</u>	Emission Factor		Notes:
	HP (hp)	CO2 (lb/hr)	
Bore/Drill Rigs	350	311.3000	Used for drillers and sleeve rigs
Crushers/Process Equipment	250	244.5000	Used for compactors
Cranes	300	180.1000	Used for cranes
	400	180.1000	
	500	180.1000	
Excavators	300	233.7000	Used for excavators
Forklifts	200	77.1000	Used for forklifts
	350	77.1000	
Graders	350	229.5000	Used for graders
Other Construction Equipment	0	10.1000	Used for manitex, spacing carts, pullers, and tensioners
	10	10.1000	
	300	254.2000	
	350	254.2000	
Other General Industrial Equipment	525	254.2000	
Rubber-Tired Dozers	650	0.1724	Used for dozers
	300	264.9000	
Tractors/Loaders/Backhoes	350	264.9000	Used for all backhoes, excavators, loaders & ditch diggers
	120	51.7000	
	200	171.7000	
	300	344.9000	
	350	344.9000	
	500	344.9000	
Source: SCAQMD Air Quality Handbook, Off-Road Emissions Sources - (http://www.aqmd.gov/ceqa/handbook/offroad/offroad.html)			
	HP (hp)	CO2 (lb/hr)	
Helicopters	650	1585.9440	Used for helicopters - No emission factor, estimated by assuming a 360 times factor of the CO emission factor.
Source: EPA 420-R-92-009 - Procedures for Emission Inventory Preparation, Volume IV, Mobile Sources, December 1992 - (http://www.ntl.bts.gov/docs/AQP.html - Table 5-7, Pg. 185)			
<u>On-Road Vehicles</u>			
	HP (hp)	CO2 (lb/hr)	
Crew & Foreman Trucks (Suburbans) (pounds/mile x 30 miles/hour)	Composite	32.985968	Used 'passenger vehicle' emfac
Pick-Up Trucks (pounds/mile) x 30 miles/hour	Composite	81.58302	Used 'delivery trucks' emfac
Heavy Duty Trucks and Truck-Mounted Equipment (pounds/mile) x 30 miles/hour	Composite	126.32014	Used 'heavy-heavy-duty trucks' emfac
Source: SCAQMD Air Quality Handbook, Emfac2007 (Ver2.3) Emission Factors (On-Road), Scenario Year 2008 - http://www.aqmd.gov/ceqa/handbook/onroad/onroad.html			

THIS PAGE IS INTENTIONALLY BLANK

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
Subtransmission Lines					
Survey					
- 1 ½-Ton Pick-Up Truck 4X4	200	3	10	815.8	1.2
- Total Survey				815.8	1.2
Roads					
- 2 1-Ton Crew Cab 4X4	300	10	2	131.9	0.7
- 1 Road Grader	350	10	10	2295.0	11.5
- 2 Track-Type Dozer	350	10	2.5	1324.5	6.6
- 1 Water Truck	350	10	10	1263.2	6.3
- Total Roads				5014.6	25.1
Pole Framing and Setting					
- 2 ¾-Ton Suburban	300	147	10	659.7	48.5
- 2 5-Ton Framing Truck 4X4	350	83	10	2526.4	104.8
- 2 30-Ton line Truck	350	83	10	2526.4	104.8
- 1 Digger Truck	500	24	10	1263.2	15.2
- 1 Water Truck	350	83	10	1263.2	52.4
- 2 Backhoe	350	147	10	6898.0	507.0
- 2 Bucket Truck	350	147	10	2601.0	191.2
- 2 Truck-Mounted Crane	350	147	10	2526.4	185.7
- 1 30-Ton Crane	500	14	10	1801.0	12.6
- 1 Cement Truck	350	3	10	1263.2	1.9
- Total Pole Framing and Setting				23328.5	1224.1

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
Material Delivery					
2 60-Foot Flat-Bed Pole Truck	350	5	8	2021.1	5.1
1 Forklift	200	5	8	616.8	1.5
Total Material Delivery				2637.9	6.6
Conductor Installation					
1 Flat-Bed Truck & Trailer (Wire Puller)	300	24	6	757.9	9.1
1 Flat-Bed Truck & Trailer (Wire Dolly)	300	24	6	757.9	9.1
2 30-Ton line Truck	300	24	5	1263.2	15.2
2 ¾-Ton Suburban	300	14	10	659.7	4.6
1 Water Truck	350	24	10	1263.2	15.2
2 Bucket Truck	350	24	6	1515.8	18.2
2 Truck-Mounted Crane	350	24	6	1515.8	18.2
Total Conductor Installation				7733.6	89.5
Restoration					
2 1-Ton Crew Cab 4X4	300	40	8	527.8	10.6
1 Water Truck	350	40	8	1010.6	20.2
Total Restoration				1538.3	30.8
Total Emissions from Subtransmission Line Construction					1377.3
Mirage Substation					
Civil					
1 Driller	Composite	50	8	1319.2	33.0
2 Crew Truck	Composite	80	2	131.9	5.3
1 14-Ton Crane	Composite	25	4	514.8	6.4
1 Dump Truck	Composite	75	6	757.9	28.4
1 Tractor	Composite	75	6	400.8	15.0

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
- 1 5-Ton Truck	Composite	15	4	505.3	3.8
- 1 Forklift	Composite	75	4	217.6	8.2
- 1 Ditch Digger	Composite	55	6	717.6	19.7
- Total Civil				4565.1	119.8
- Electrical					
- 2 Manlift	Composite	100	6	416.4	20.8
- 1 Pick-Up Truck	Composite	110	2	163.2	9.0
- 1 14-Ton Crane Truck	Composite	90	6	757.9	34.1
- 2 Crew Truck	Composite	110	2	131.9	7.3
- 1 150-Ton Crane	Composite	60	6	772.2	23.2
- 1 5-Ton Truck	Composite	50	2	252.6	6.3
- 1 Forklift	Composite	100	6	326.4	16.3
- 2 Carryall Vehicle	Composite	110	2	505.3	27.8
- 1 Support Truck	Composite	25	2	252.6	3.2
- Total Electrical				3578.6	147.9
- Transformer Installation					
- 2 Carryall Vehicle	Composite	22	6	1515.8	16.7
- 1 Manlift	Composite	20	6	208.2	2.1
- 1 Forklift	Composite	22	6	326.4	3.6
- 1 50-Ton Crane	Composite	15	6	772.2	5.8
- 2 Crew Truck	Composite	22	2	131.9	1.5
- Total Transformer Installation				2954.6	29.6
- Maintenance					
- 1 Foreman Truck	Composite	40	2	66.0	1.3
- 1 Manlift	Composite	40	6	208.2	4.2
- 2 Crew Truck	Composite	110	2	131.9	7.3
- Total Maintenance				406.1	12.7

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
Test					
1 Pick-Up Truck	Composite	110	2	163.2	9.0
Total Test				163.2	9.0
Total Mirage Substation					319.04
<u>Concho Substation</u>					
Electrical					
1 Carryall Vehicle	Composite	34	2	252.6	4.3
Test					
1 Pick-Up Truck	Composite	34	2	163.2	2.8
Total Concho Substation					7.07
<u>Indian Wells Substation</u>					
Electrical					
1 Carryall Vehicle	Composite	50	2	252.6	6.3
Test					
1 Pick-Up Truck	Composite	50	2	163.2	4.1
Total Indian Wells Substation					10.4
<u>Santa Rosa Substation</u>					
Electrical					
1 Carryall Vehicle	Composite	40	2	252.6	5.1

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
Test					
1 Pick-Up Truck	Composite	40	2	163.2	3.3
Total Santa Rosa Substation					8.3
Devers Substation					
Civil					
1 Driller	Composite	2	8	1319.2	1.3
1 Crew Truck	Composite	5	2	66.0	0.2
1 Dump Truck	Composite	5	6	757.9	1.9
1 Tractor	Composite	5	6	400.8	1.0
Total Civil				2543.9	4.4
Electrical					
1 Manlift	Composite	45	6	208.2	4.7
1 Pick-Up Truck	Composite	60	2	163.2	4.9
1 Crew Truck	Composite	60	2	66.0	2.0
1 150-Ton Crane	Composite	10	6	772.2	3.9
1 Forklift	Composite	40	6	326.4	6.5
1 Carryall Vehicle	Composite	60	2	252.6	7.6
Total Electrical				1788.6	29.5
Maintenance					
1 Foreman Truck	Composite	5	2	66.0	0.2
1 Crew Truck	Composite	10	2	66.0	0.3
Total Maintenance				131.9	0.5

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
Test					
1 Pick-Up Truck	Composite	20	2	163.2	1.6
Total Test				163.2	1.6
Total Devers Substation					36.0
Eisenhower Substation					
Civil					
1 Driller	Composite	5	8	1319.2	3.3
1 Crew Truck	Composite	15	2	66.0	0.5
1 Dump Truck	Composite	15	6	757.9	5.7
1 Tractor	Composite	15	6	400.8	3.0
1 Ditch Digger	Composite	5	6	717.6	1.8
Total Civil				3261.5	14.3
Electrical					
1 Manlift	Composite	35	6	208.2	3.6
1 Crew Truck	Composite	45	2	66.0	1.5
1 150-Ton Crane	Composite	20	6	772.2	7.7
1 Forklift	Composite	45	6	326.4	7.3
1 Carryall Vehicle	Composite	45	2	252.6	5.7
Total Electrical				1625.4	25.9
Maintenance					
1 Foreman Truck	Composite	5	2	66.0	0.2
1 Crew Truck	Composite	10	2	66.0	0.3
Total Maintenance				131.9	0.5

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
Test					
1 Pick-Up Truck	Composite	45	2	163.2	3.7
Total Test				163.2	3.7
Total Eisenhower Substation					44.3
Farrell Substation					
Civil					
1 Driller	Composite	10	8	1319.2	6.6
1 Crew Truck	Composite	20	2	66.0	0.7
1 Dump Truck	Composite	20	6	757.9	7.6
1 Tractor	Composite	20	6	400.8	4.0
1 Ditch Digger	Composite	10	6	717.6	3.6
Total Civil				3261.5	22.4
Electrical					
1 Manlift	Composite	40	6	208.2	4.2
1 Crew Truck	Composite	55	2	66.0	1.8
1 150-Ton Crane	Composite	25	6	772.2	9.7
1 Forklift	Composite	55	6	326.4	9.0
1 Carryall Vehicle	Composite	55	2	252.6	6.9
Total Electrical				1625.4	31.6
Maintenance					
1 Foreman Truck	Composite	5	2	66.0	0.2
1 Crew Truck	Composite	10	2	66.0	0.3
Total Maintenance				131.9	0.5

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
Test					
1 Pick-Up Truck	Composite	55	2	163.2	4.5
Total Test				163.2	4.5
Total Farrell Substation					59.0
<u>Garnet Substation</u>					
Electrical					
1 Carryall Vehicle	Composite	16	2	252.6	2.0
Test					
1 Pick-Up Truck	Composite	16	2	163.2	1.3
Total Garnet Substation					3.3
<u>Thornhill Substation</u>					
Electrical					
1 Carryall Vehicle	Composite	40	2	252.6	5.1
Test					
1 Pick-Up Truck	Composite	40	2	163.2	3.3
Total Thornhill Substation					8.3
<u>Tamarisk Substation</u>					
Civil					
1 Crew Truck	Composite	5	2	66.0	0.2
1 Dump Truck	Composite	5	6	757.9	1.9
1 Tractor	Composite	5	6	400.8	1.0
Total Civil				1224.7	3.1

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
Electrical					
1 Manlift	Composite	5	6	208.2	0.5
1 Pick-Up Truck	Composite	40	2	163.2	3.3
1 Crew Truck	Composite	40	2	66.0	1.3
1 150-Ton Crane	Composite	2	6	772.2	0.8
1 Forklift	Composite	5	6	326.4	0.8
1 Carryall Vehicle	Composite	40	2	252.6	5.1
Total Electrical				1788.6	11.7
Maintenance					
1 Foreman Truck	Composite	1	2	66.0	0.0
2 Crew Truck	Composite	2	2	131.9	0.1
Total Maintenance				197.9	0.2
Test					
1 Pick-Up Truck	Composite	30	2	163.2	2.4
Total Test				163.2	2.4
Total Tamarisk Substation					17.4

THIS PAGE IS INTENTIONALLY BLANK

Table F-24. Subtransmission Line Emission Factors

Off-Road Construction Equipment	Emission Factors		Notes:
	HP (hp)	CO2 (lb/hr)	
Aerial Lifts	Composite	34.7000	Used for manlifts
Bore/Drill Rigs	Composite	164.9000	Used for drillers and sleeve rigs
Cranes	500	180.1000	Used for all cranes
	Composite	128.7000	
Excavators	Composite	119.6000	Used for excavators and ditch diggers
Forklifts	200	77.1000	Used for forklifts
	Composite	54.4000	
Graders	350	229.5000	Used for graders
Off-Highway Trucks	Composite	260.1000	Used for all diesel trucks & carryall vehicles
Other Material Handling Equipment	Composite	141.2000	Used for cable puller & conductor tensioner
Other Construction Equipment	Composite	122.8000	Used for cable dollies
Rubber-Tired Dozers	350	264.9000	Used for dozers
Tractors/Loaders/Backhoes	350	344.9000	Used for all backhoes & ditch diggers
	Composite	66.8000	
Source: SCAQMD Air Quality Handbook, Off-Road Emissions Sources - (http://www.aqmd.gov/ceqa/handbook/offroad/offroad.html)			
On-Road Vehicles			
	HP (hp)	CO2 (lb/hr)	
Crew & Foreman Trucks (Suburbans) (pounds/mile x 30 miles/hour)	Composite	32.985968	Used 'passenger vehicle' emfac
Pick-Up Trucks (pounds/mile) x 30 miles/hour	Composite	81.58302	Used 'delivery trucks' emfac
Heavy Duty Trucks and Truck-Mounted Equipment (pounds/mile) x 30 miles/hour	Composite	126.3201435	Used 'heavy-heavy-duty trucks' emfac
Source: SCAQMD Air Quality Handbook, Emfac2007 (Ver2.3) Emission Factors (On-Road), Scenario Year 2008 - http://www.aqmd.gov/ceqa/handbook/onroad/onroad.html			

THIS PAGE IS INTENTIONALLY BLANK

Table F-25. Equipment Exhaust During Telecommunication Construction - CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
Mirage-Santa Rosa					
Cable Construction					
- 2 Bucket Truck	Composite	5	8	2021.1	5.1
- 1 Pick-Up	Composite	5	8	652.7	1.6
- 1 2-Axle Trailer	Composite	5	8	1129.6	2.8
- Total Cable Construction				3803.4	9.5
Receive and Loadout					
- 1 5-Ton Forklift	Composite	1	8	435.2	0.2
- 1 Pick-Up	Composite	1	8	652.7	0.3
- Total Receive and Loadout				1087.9	0.5
Clean-Up					
- 2 Bucket Truck	Composite	1	8	2021.1	1.0
- 1 Pick-Up	Composite	1	8	652.7	0.3
- Total Clean-Up				2673.8	1.3
- Total Mirage Santa Rosa					11.39
Farrell-Garnet					
Cable Construction					
- 2 Bucket Truck	Composite	18	8	2021.1	18.2
- 1 Pick-Up	Composite	18	8	652.7	5.9
- 1 2-Axle Trailer	Composite	18	8	1129.6	10.2
- Total Cable Construction				3803.4	34.2
Receive and Loadout					
- 1 5-Ton Forklift	Composite	1	8	435.2	0.2
- 1 Pick-Up	Composite	1	8	652.7	0.3
- Total Receive and Loadout				1087.9	0.5
Clean-Up					
- 2 Bucket Truck	Composite	1	8	2021.1	1.0
- 1 Pick-Up	Composite	1	8	652.7	0.3
- Total Clean-Up				2673.8	1.3
- Total Farrel Garnet					36.11
Devers					
Equipment Installation					
- 2 Pick-Up	Composite	6	8	1305.3	3.9
- Total Cable Construction				1305.3	3.9
Circuit Installation					
- 2 Pick-Up	Composite	6	8	1305.3	3.9
- Total Circuit Installation				1305.3	3.9

Table F-25. Equipment Exhaust During Telecommunication Construction - CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
Clean-Up					
1 Pick-Up	Composite	1	8	652.7	0.3
Total Clean-Up				652.7	0.3
Total Devers					8.16
Mirage					
Equipment Installation					
2 Pick-Up	Composite	6	8	1305.3	3.9
Total Cable Construction				1305.3	3.9
Circuit Installation					
2 Pick-Up	Composite	6	8	1305.3	3.9
Total Circuit Installation				1305.3	3.9
Clean-Up					
1 Pick-Up	Composite	1	8	652.7	0.3
Total Clean-Up				652.7	0.3
Total Mirage					8.16
Tamarisk					
Equipment Installation					
2 Pick-Up	Composite	6	8	1305.3	3.9
Total Cable Construction				1305.3	3.9
Circuit Installation					
2 Pick-Up	Composite	6	8	1305.3	3.9
Total Circuit Installation				1305.3	3.9
Clean-Up					
1 Pick-Up	Composite	1	8	652.7	0.3
Total Clean-Up				652.7	0.3
Total Tamarisk					8.16
Eisenhower					
Equipment Installation					
2 Pick-Up	Composite	6	8	1305.3	3.9
Total Cable Construction				1305.3	3.9
Circuit Installation					
2 Pick-Up	Composite	6	8	1305.3	3.9
Total Circuit Installation				1305.3	3.9
Clean-Up					
1 Pick-Up	Composite	1	8	652.7	0.3

Table F-25. Equipment Exhaust During Telecommunication Construction - CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
- Total Clean-Up				652.7	0.3
- Total Eisenhower					8.16
Concho					
- Equipment Installation					
- 2 Pick-Up	Composite	6	8	1305.3	3.9
- Total Cable Construction				1305.3	3.9
- Circuit Installation					
- 2 Pick-Up	Composite	6	8	1305.3	3.9
- Total Circuit Installation				1305.3	3.9
- Clean-Up					
- 1 Pick-Up	Composite	1	8	652.7	0.3
- Total Clean-Up				652.7	0.3
- Total Concho					8.16
Indian Wells					
- Equipment Installation					
- 2 Pick-Up	Composite	6	8	1305.3	3.9
- Total Cable Construction				1305.3	3.9
- Circuit Installation					
- 2 Pick-Up	Composite	6	8	1305.3	3.9
- Total Circuit Installation				1305.3	3.9
- Clean-Up					
- 1 Pick-Up	Composite	1	8	652.7	0.3
- Total Clean-Up				652.7	0.3
- Total Indian Wells					8.16
Santa Rosa					
- Equipment Installation					
- 2 Pick-Up	Composite	6	8	1305.3	3.9
- Total Cable Construction				1305.3	3.9
- Circuit Installation					
- 2 Pick-Up	Composite	6	8	1305.3	3.9
- Total Circuit Installation				1305.3	3.9
- Clean-Up					
- 1 Pick-Up	Composite	1	8	652.7	0.3
- Total Clean-Up				652.7	0.3
- Total Santa Rosa					8.16

Table F-25. Equipment Exhaust During Telecommunication Construction - CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
Thornhill					
- Equipment Installation					
- 1 Pick-Up	Composite	6	8	652.7	2.0
- Total Cable Construction				652.7	2.0
-					
- Circuit Installation					
- 1 Pick-Up	Composite	6	8	652.7	2.0
- Total Circuit Installation				652.7	2.0
-					
- Clean-Up					
- 1 Pick-Up	Composite	1	8	652.7	0.3
- Total Clean-Up				652.7	0.3
- Total Thornhill					4.24
Garnet					
- Equipment Installation					
- 1 Pick-Up	Composite	6	8	652.7	2.0
- Total Cable Construction				652.7	2.0
-					
- Circuit Installation					
- 1 Pick-Up	Composite	6	8	652.7	2.0
- Total Circuit Installation				652.7	2.0
-					
- Clean-Up					
- 1 Pick-Up	Composite	1	8	652.7	0.3
- Total Clean-Up				652.7	0.3
- Total Garnet					4.24
Farrell					
- Equipment Installation					
- 1 Pick-Up	Composite	6	8	652.7	2.0
- Total Cable Construction				652.7	2.0
-					
- Circuit Installation					
- 1 Pick-Up	Composite	6	8	652.7	2.0
- Total Circuit Installation				652.7	2.0
-					
- Clean-Up					
- 1 Pick-Up	Composite	1	8	652.7	0.3
- Total Clean-Up				652.7	0.3
- Total Farrell					4.24

Table F-25. Equipment Exhaust During Telecommunication Construction - CO2 Exhaust Emissions

Construction	HP	Duration (days)	Usage (hour/day)	CO2 Emissions (lb/day)	CO2 Emissions (tons/project)
EDOM Hill					
- Equipment Installation					
- 1 Pick-Up	Composite	6	8	652.7	2.0
- Total Cable Construction				652.7	2.0
- Circuit Installation					
- 1 Pick-Up	Composite	6	8	652.7	2.0
- Total Circuit Installation				652.7	2.0
- Clean-Up					
- 1 Pick-Up	Composite	1	8	652.7	0.3
- Total Clean-Up				652.7	0.3
- Total EDOM Hills					4.24
Palm Springs					
- Equipment Installation					
- 1 Pick-Up	Composite	6	8	652.7	2.0
- Total Cable Construction				652.7	2.0
- Circuit Installation					
- 1 Pick-Up	Composite	6	8	652.7	2.0
- Total Circuit Installation				652.7	2.0
- Clean-Up					
- 1 Pick-Up	Composite	1	8	652.7	0.3
- Total Clean-Up				652.7	0.3
- Total Palm Springs					4.24
TOTAL EMISSIONS DURING CONSTRUCTION					125.8

THIS PAGE IS INTENTIONALLY BLANK

Table F-26. Telecommunication Equipment Emission Factors

<u>Off-Road Construction Equipment</u>	Emission Factors		Notes:
	HP (hp)	CO2 (lb/hr)	
Forklifts	Composite	54.4000	Used for forklifts
Off-Highway Trucks	Composite	260.1000	Used for all diesel trucks & carryall vehicles
Other Material Handling Equipment	Composite	141.2000	Used for cable puller & conductor tensioner
Source: SCAQMD Air Quality Handbook, Off-Road Emissions Sources - (http://www.aqmd.gov/ceqa/handbook/offroad/offroad.html)			
<u>On-Road Vehicles</u>			
	HP (hp)	CO2 (lb/hr)	
Crew & Foreman Trucks (Suburbans) (pounds/mile x 30 miles/hour)	Composite	32.985968	Used 'passenger vehicle' emfac
Pickup Trucks (pounds/mile) x 30 miles/hour	Composite	81.58302	Used 'delivery trucks' emfac
Heavy Duty Trucks and Truck-Mounted Equipment (pounds/mile) x 30 miles/hour	Composite	126.3201435	Used 'heavy-heavy-duty trucks' emfac
Source: SCAQMD Air Quality Handbook, Emfac2007 (Ver2.3) Emission Factors (On-Road), Scenario Year 2008 - http://www.aqmd.gov/ceqa/handbook/onroad/onroad.html			

THIS PAGE IS INTENTIONALLY BLANK

Notes

Devers-Mirage 115 kV Construction

AQ Calculations by: Eric Rivero-Montes
 Last Calculation Date: 11/20/2007
 Project Description: As provided in PEA
 Equipment List: As provided in PEA
 Provided by:
 Date Provided:

Schedule
 Provided by:
 Date Provided

Construction Element	Number of Personnel	Number of Days	Start Date	Finish Date	Equipment Requirements		HP	Hrs/Day	Notes
					Number	Description			
Roads	3	10			2	Crew Truck (gasoline)	200	2	ALW assumed HP
		10			2	Light Truck	180	2	ALW assumed HP
		10			1	Crawler D6	250	10	ALW assumed HP
		10			1	Crawler D8	250	10	ALW assumed HP
		10			1	Motor Grader	250	5	ALW assumed HP
		10			1	Water Truck	250	2	ALW assumed HP
Subtransmission Line	30	171			2	Crew Truck (gasoline)	200	10	ALW assumed HP
		107			2	Line Truck	250	10	ALW assumed HP
		107			2	Light Truck	180	10	ALW assumed HP
		171			2	Bucket Truck	250	10	ALW assumed HP
		107			2	Truck-Mounted Crane	250	10	ALW assumed HP
		24			1	Conductor-Pulling Machine	300	10	ALW assumed HP
		24			1	Tensioner (gasoline)	300	10	ALW assumed HP

Construction Element	Number of Personnel	Number of Days	Start Date	Finish Date	Equipment Requirements	HP	Hrs/Day	Notes
		14			1 30-Ton Crane	250	10	ALW assumed HP
		171			2 Backhoe	250	10	ALW assumed HP
		24			1 Drilling Rig	500	10	ALW assumed HP
		107			1 Water Truck	250	10	ALW assumed HP
		3			1 Concrete Truck	500	10	ALW assumed truck needed
		0			0 Flat-Bed Pole Truck	500	10	ALW assumed truck needed
Staging areas		0			0 Crane (diesel)	250	10	ALW assumed equipment needed
Staging areas		0			0 980 Loader (diesel)	250	10	ALW assumed equipment needed
Staging areas		0			0 Forklift (diesel)	250	10	ALW assumed equipment needed
Telecommunications								
Equipment Construction	2	13			2 Van (gasoline)	200	7	ALW assumed HP
Overhead Construction	4	50			1 Bucket Truck	250	8	ALW assumed HP
		50			1 Reel Truck	250	8	ALW assumed HP
Underground Conduit	3	5			1 Flat-Bed Truck	250	1	ALW assumed HP
		5			1 Backhoe	250	8	ALW assumed HP
		5			1 Stake-Bed Truck	250	2	ALW assumed HP
		5			1 Crew Truck (gasoline)	200	2	ALW assumed HP
	4	2			1 Bucket Truck	250	2	ALW assumed HP
		2			1 Reel Truck	250	2	ALW assumed HP