California Dairy-Sourced RNG Interconnection Update

DAIRY DIGESTER DEVELOPER CASE STUDY

Daryl Maas, CEO of Maas Energy Works

November 11, 2019




Overview

- State of Dairy Digester Industry
- RNG Injection Case Study
- Utility Injection Standards
- Recommendations







Shift from Power to Gas



Digesters Built in California

All Others

Maas Energy Works

Still Water Dairy, Sept 2019 - K&M Visser Dairy, Sept 2019 - Vander Poel Dairy, August 2019
















New Hope Dairy, July 2013
Shut Down, June 2016
Acquired by MEW Sept 2018

ABEC #1 Bidart - Old River Dec 2014

- Van Warmerdam Dairy, May 2013 🦊








Schott Dairy Little Rock Dairy Simoes Dairy Construction 90% Complete Sousa & Sousa Dairy JR Dairy Online Blue Moon Dairy Construction 90% Complete Northstar Dairy Cornerstone Dairy Online Hettinga Dairy Calgren Dairy Fuels LLC Pixley Dairy Construction 40% Complete Circle A Dairy Online Robert Van Der Eyk Dairy Legacy Ranch Dairy K&M Visser Dairy 4K Dairy Riverview Dairy Construction Online 80% Complete Vander Poel Dairy Phase 1 Constructed Biogas Pipeline Phase 2 Planned Biogas Pipeline

Calgren Dairy Fuels Cluster

- Maas EnergyWorks LeadDeveloper
- 8 Digesters online injecting RNG to SoCalGas Pipeline
- Expanding to 20+ total dairies
- ~4M GGE/year CNG




Digesters	\$ 30,075,000
Biogas Cleanup	\$ 11,200,000
Pipeline	\$ 6,050,000
Interconnection	\$ 3,700,000
Total	\$ 51,025,000



Virtual
Pipeline
Online!





Thoughts and Recommendations



- AB-2313
 - Reimbursement
 - Based on injection date
 - Limited pool of funds (raise bar)
- Pilot Project
 - Paid by utility directly
 - One-time cycle
- Expansions (Critical!)
 - AB-2313 eligibility for additional investments beyond Pilot Project

Interconnect Funding



Interconnect Case Studies

		Calgren Dairy Fuels	Lakeside Pipeline	Merced Pipeline
Regs	Utility	SoCalGas	SoCalGas	PG&E
	Tariff	Rule 39 (old)	Rule 39 (new)	Rule 21 (new)
	Pilot Project?	No	Yes	Yes
Gas Spec	Oxygen	0.20%	0.20%	0.10%
	CO-2	3%	3%	1%
	H2S	4 ppm	4 ppm	4 ppm
	Nitrogen (inerts)	4%	4%	n/a
	BTU	990 BTU	970 BTU*	980**
l Method I	Engineered By	Owner	Utility	Utility
	Construciton By	Owner	Utility	Utility
Results	Total Time	23 Months	35 Months (est)	35 Months (est)
	Total Cost	\$1,746,039	\$2,071,825 (est)	\$1,700,000 (est)

^{*} higher due to other limits

^{**} project specific

Statewide Tariff Recommendations

- II.B. states SoCalGas will use the existing Interconnect Collectible System Upgrade Agreement
 - Delays in establishing collective
 - Impossible warranty provisions (fixed with onetime advice letter)
 - Agreement needs modification (PG&ETBD)
- Self-Design (CPUC D.07-08-029 section 4.13.2)
 - III.A. (bottom of page 7) states that <u>utility</u> will perform the design engineering.
 - In the tariff F 2 (c) states utility "will design and engineer....or provide specifications, inspection, and oversight...if applicable"
 - Interconnector's sole discretion must be explicit

